

15-007-20383

State Geological Survey

KANSAS DRILLERS LOG

S. 8 T. 33S R. 15 ^{XX} W
 Loc. C NE NW
 County Barber

API No. 15 —————
 County _____ Number _____

Operator
 Beren Corporation

Address
 970 Fourth Financial Center, Wichita, KS 67202


Well No. 1 Lease Name Goforth

Footage Location
 660 feet from (N) (X) line 1980 feet from (X) (W) line

Principal Contractor Xplor Drilling Company Geologist Don Beauchamp

Spud Date Jan. 2, 1976 Total Depth 4150' P.B.T.D.

Date Completed Jan. 12, 1976 Oil Purchaser



Elev.: Gr. 1764
 DF 1769 KB 1772

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	40	274'	Common	275	3% C.C., 2% Gel
Production	7 7/8"	4 1/2"	10.5	4150'	Common	300	18% Salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF		

Disposition of gas (vented, used on lease or sold) _____ Producing interval (s) _____

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas

ator

Beren Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

1

Lease Name

GOFORTH

S 8 T 33S R 15 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Soil & Shale	0	60		
Red Bed Shale	60	601		
Shale & Shells	601	981		
Shale	981	1507		
Shale & Shells & Anhydrite	1507	1907		
Shale & Lime	1907	2170		
Lime	2170	2208		
Shale & Lime	2208	2352		
Lime	2352	2633		
Lime & Shale	2633	3265		
Lime	3265	3400		
Topeka	3400	3405		
Lime	3405	3530		
Topeka, Lime & Shale	3530	3560		
Lime	3560	3820		
Shale & Lime	3820	4150		
T.D.	4150			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Don Beauchamp
Signature

Don Beauchamp, Geologist
Title

April 26, 1977
Date

Date