

8-33-15W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CHAMPLIN OIL & REFINING CO.
Farm- Winter No. 1

SEC. 8 T. 33 R. 15W
C NE SE NW

Total Depth. 5081'
Comm. 5-6-63 Comp. 5-23-63
Shot or Treated.
Contractor. Red Tiger Drilling Co.
Issued. 9-14-63

County Barber
KANSAS



CASING:
8 5/8" 321.43' cem w/225 sx.

Elevation. 1812' DE

Production. Dry

Figures indicate Bottom of Formations.

cellar clay	20
shale lime shells	195
shale & shells	800
redbed & shale	1040
shale shells & redbed	1284
shale & gypsum strks.	1665
shale & shells	1740
Anhydrite & lime	1920
lime shells & shale	2080
lime & shale	3620
lime	3685
lime & chalk	3750
shale & lime	4096
lime	4775
lime & shale	4815
lime	4893
lime & chert	4955
lime shale & chert	4990
chert & lime	5010
lime	5080
lime ?	5081
Total Depth	
TOPS: LOG	
Elgin	3759
Heebner	3956
Toronto	4018
Douglas	4042
Lansing	4092
Base Kansas City	4580
Marmaton	4588
Cherokee	4696
Mississippi	4704
Woodford	4840
Viola	4874
Simpson	5019
Dolomite	5025
Simpson Sand	5052

DST #4 4916-39' Op 2 hrs. fair blow
to strong blow/20", Dec.
to blok at end Rec. 420' gas, 60' GCM,
120' GCMW, 420' GCSW, FP: 27-298#, SIP
1760#/30"--1733#/60", HP 2688-2642 lb.
BHT: 120 deg. F.

DST #1 4610-92' Op 2 hrs. good blow,
GTS 2", F/635 MCF, G/435 MCF/10", G/
392 MCF/20", G/310 MCF/30", G/139 MCF/
60", G/104 MCF/90 min. TSTM-115" Rec.
120' SGCM, FP 99-45#, SIP: 1688#/30",
588#/60", HP 2532-2487, BHT: 116 deg. F.

DST #2 4801-60' Op 60", w/very wk blow/
1" & died, Fl. tool after 30" w/no blow,
Rec. 15' mud, FP 9-9#, ISIP 18#/60", BHT:
118 deg. F.

DST #3 4866-93' Op 60", very wk blow
for 10" & died, Fl. tool at 30", very
wk. blow 1", Rec. 20' mud, FP 9-9#, ISIP
27#/30", FSIP 18#/60", BHT: 119 deg. F.

