

Plotted
~~15-33-15W~~


SUPERIOR OIL CO. OF CALIF.
Mitchell No. 1.

SEC. 15
NWc SW

T. 33 R. 15 W

Total Depth. 5462'
Comm. 8-11-43 Comp. 9-20-43
Shot or Treated.
Contractor.
Issued. 10-2-43

County. Barber



CASING:
10^{3/4}" 422'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

red bed & shale	195	lime sft	4440
sand & shale	375	lime	4572
shale red	427	lime sft	4580
red bed	530	lime	4780
red bed & shale	1205	lime & shale	4831
shale & shells	1400	lime	4860
shale & salt	1520	lime & shale	4928
shale & shells	1705	lime	4940
lime brkn & shale	1860	shale w/lime strks	4960
shale & anhydrite	1995	shale & lime	5000
anhydrite	2075	shale	5095
lime	2120	shale & lime	5113
anhydrite & lime	2190	shale	5140
lime	2285	shale & lime	5169
shale	2340	shale & sand	5175
lime brkn & shale	2435	shale & lime	5231
shale & lime	2470	lime w/chert strks	5254
Florence Flint	2492	lime cherty	5270
shale	2505	lime & chert	5297
brkn sdy lime	2550	lime & shale	5319
sdylime	2587	shale	5355
flint	2592	shale & sand	5432
lime sdy	2603	lime	5462
lime brkn & shale	2680	Total Depth.	
lime & shale	2725		
lime brkn	2757		
sand	2765	Tops:	
shale & lime	2780	Florence Flint	2470
shale	2795	Topeka	3260
shale & shells	2895	Lansing	4227
shale & lime	2940	Mississippi	4850
lime brkn	3035	Misener	5147
shale & shells	3109	Viola	5195
shale	3150	Simpson	5316
lime brkn	3170	Arbuckle	5432
lime brkn sdy	3182		
shale & shells	3325	No shows	
lime	3380		
shale	3390		
lime	3667		
shale	3675		
lime	3755		
shale & lime	3790		
lime	3900		
lime & sand	3955		
lime	4035		
lime & shale	4075		
lime	4115		
lime w/shale strks	4170		
lime & shale	4210		
lime	4270		
lime sft	4290		
lime & shale	4330		
lime	4347		
sand	4350		
lime	4431		