

36-33-15W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
50S East Murdock, Wichita, Kansas

Company- CHAMPLIN OIL & REFINING CO.
Farm- Davis Ranch "H" No. 2

SEC. 36 T. 33 R. 15W
SW NW SE

Total Depth. 4935'
Perm. 5-8-61 Comp. 5-30-61
Well Treated.
Director. H-30, Inc.
Dated. 10-14-61

County Barber
KANSAS



Elevation. 1785' DF

Production. 3,600,000 CFG

CASING:

13 3/8" 204' cem w/225 sx.
8 5/8" 871' cem w/100 sx.
5 1/2" 4935' cem w/50 sx.

Figures Indicate Bottom of Formations.

top soil & clay	40
red shale, gyp	120
gyp & shale	204
red shale & shells	370
dry drilling	900
reaming to 12 1/4"	204-872
red bed, shale & shells	1185
shale & shells	1800
lime & shale	2405
lime	2520
shale & lime	2915
shale & shells	3010
shale & lime	3205
lime	3365
lime & shale	3550
lime	3885
shale & lime	3960
lime & shale	4015
shale & lime	4050
lime & shale	4320
lime	4560
lime & shale	4865
lime	4910
Mississippi lime	4935 RTD
Total Depth	

TOPS: ELECTRIC

Heebner	4049
Toronto	4064
Douglas	4078
Lansing-Kansas City	4248
Base Kansas City	4732
Manhattan	4744
Cherokee	4827
Mississippian	4868

Perforated Miss. 4869-75'
Fracture treated w/15,000 gal. & 25,000# sand.

DST #1 4868-4910' op 100 mins, GTS 1 1/2 mins.
G/2,000 MCF/5 min, G/3,690 MCF/30 min,
G/4,160 MCF/45 min. - stabilized.