

~~Norman - Lang.~~
Field ~~Bruno~~ NE

State Kansas

County Meade

Company Shamrock

Farm Clara Vail, et al

Well No. 1

Sec. 15

Twp. Blk.

33S

Range Survey

30W

~~1000'~~ fr N ~~2000'~~ fr E fr S fr W
of SW NE

Contractor Service Drlg.

Remarks

Comm. 6-30-55

Comp. 9-7-55

Elev. 2731

T. D. 5802

P. B.

Pay 4553-57 (Lang)

I. P. 188 BOPD

R. P.

Casing Record: 133/8

7

20 103/4 640/500

5 1/2 4605/150

16 95/8 2675/800

Same.

6-29-55 RURT

Tops

Bm Dda 2665

C.G. 3136

Lang 4544

Marm 5179

JUL 6 1955 ϕ 2450

JUL 13 1955 ϕ 3595

JUL 20 1955 DST (Lang) 4545-4624 mod 5691

op/bk gts in 25 mi. to 1 mi. Chas. 5760

See 360' hwy in 490' W.C.

2070' gts in 20 mi. 450' SW

FP 4950/1280, BN 1380/30 NH 2208

hwy to 1 mi. to 1 mi.

DST 4545-53 up 1 mi. 5 mi.

str 610' gts in 6 mi. See g-27 mi. in

14 mi., 21 mi. in 20 mi. 14 mi.

in 1 mi. 5 mi., See 3700' Alvin, 2 pipe

unloaded 3160' free oil, 180' ocm,

360' SW. FP 200-938, BN 1280/30

NH 2208 W.O.

JUL 27 1955 Run Sch to 4633

ϕ 5414

AUG 3 1955

45708-30 rec 19' 6"
1' tite lm.
1' 4" sh.
8" lm
10' 6" cotton sh.

Schls. tops by
Her. 2665
Kri 2742
Wing 2793
U. F. & Pil 2854
L. " " 2924
Flume 2972
C.G. 3143
Shawnee 4393
Lang 4545
Mum 5192
Cik 5356

45730-60 rec 30'
17' blk cotton sh.
6' Shaly glass lm w/ thin lam. of tite sd
4' gm sh.
3' blk cotton sh.

45760-5802 RTD rec 32' of
interbedded tite lm. & sh. atoken 5469
rec 5802 5 1/2 @ 4605/

AUG 10 1955

~~Rec~~ run G.R. log to 4571 chn 5763

6/4558-62 thy w/ rest @ 4555 & log
w/ 93.4 ft @ 4565 p 24/4553-570

2 1/2" thy to 4561 MOR, RUSwallowing Unit

Swab 4660 @ 276W in 4 1/2 hrs

AUG 17 1955 SICP 130 #

Swab 3260 @ 226W in 3 hrs.

SICP 220 #

Pop

AUG 24 1955

pumped 62.63 BO used
24 Bubs in 8 hrs.

calc put 188 BOPD, 72 BWPD

Gvty 370 ~~schl~~

AUG 31 1955

SEP 7 1955

4