


1-84W 1962Gr ELEV. 1970DF 1972KB  
 MAP NO. \_\_\_\_\_  
 STATE Kans COUNTY Clark SEC. 16 TWP. 33S RGE. 21W  
 OPERATOR Ashland Oil & Refining Co loc. App SW NE SW  
 WELL NO. 1 FARM NAME Folks Unit 1650 FT. FROM S LINE  
 POOL Harper Ranch 1650 FT. FROM W LINE  
 FR. 11/13/61 SPUD \_\_\_\_\_ COMP. 1/9/62

CONT./GEOL. Graham-Michaelis Drlg Tools Rig #1

| NAME PRODUCING INTERVAL |                        | COMPLETION RECORD<br>FROM - TO | PERF. W/HOLES | TREATMENT RECORD        |
|-------------------------|------------------------|--------------------------------|---------------|-------------------------|
| a                       | <u>Morr</u>            | <u>5374-86</u>                 | <u>48</u>     | <u>500A + 500# Salt</u> |
| b                       | <u>Chest</u>           | <u>5408-30</u>                 | <u>66</u>     | <u>1000A</u>            |
| c                       | <u>(Commingle gas)</u> |                                |               |                         |
| d                       | <u>4 PT OF Ga</u>      |                                |               |                         |



a I. P. OIL/DIST. 0 WTR. 0 GAS 37,000 M.C.F.P.D. (+ est 20 M.B Dist) hrs. 24  
 b " " " " " "  
 c " " " " " "  
 d \_\_\_\_\_

D & A ( )

| SIPH#         |             | FI TP #                          | FI CP#        | SIBHP       |
|---------------|-------------|----------------------------------|---------------|-------------|
|               |             |                                  |               | <u>5492</u> |
| GOR.          |             | GR.                              | PSTD          | TD          |
|               |             |                                  |               |             |
| SIZE          | DEPTH       | CASING - CEMENT RECORD<br>W/SAX. | SIZE          | DEPTH       |
| <u>8 5/8"</u> | <u>580</u>  | <u>450</u>                       | <u>2" tbg</u> | <u>5424</u> |
| <u>4 1/2"</u> | <u>4584</u> | <u>156</u>                       |               |             |

OPERATOR Ashland Oil & Refining WELL NO. 1 Folks Unit ELEV. 1972KB

| SAMPLE TOPS           | DEPTH | SUB SEA | ELEC. TOPS | DEPTH | SUB SEA |
|-----------------------|-------|---------|------------|-------|---------|
| KB TOPS & DATUM       |       |         | Log        |       |         |
| Hb 4295               |       |         | Hb         | 4304  | -2332   |
| Tor 4348              |       |         | Tor        | 4341  | -2369   |
| Lans 4517             |       |         | Lans       | 4527  | -2555   |
| TD (Chest) 5492 -3520 |       |         | Marm       | 5082  | -3110   |
|                       |       |         | Chero      | 5212  | -3240   |
|                       |       |         | Morr       | 5364  | -3392   |
|                       |       |         | Chest      | 5391  | -3419   |
|                       |       |         | LTD        | NA    |         |

DST #1 (Morr) 5367-79, op 20", GTS/1", Ga 3310 Mcfgpd/5",  
 Ga 4260 Mcfgpd/10", Ga 5210 Mcfgpd/15", Rec 1 Gal Dist  
 Gr55°, IBHP 1820#/30", IFP 1830#, FFP 1830#, FBHP 1830#/  
 30".

DST #2 (Chest) 5387-5410, op 1 1/2 hrs, R 30' M, IBHP 145#/30",  
 IFP 0#, FFP 15#, FBHP 140#/30".

RTD 5492. Log. 4 1/2" @ 4584 w/156 sx. 66/5408-30 (Chest)  
 Tbg set @ 5424, 1000A, SITP 1550#, SICP 1550#, Est ga  
 1,450 Mcfgpd, 24/64" ck, FTP 1175#, FCP 1300#, Ga  
 3500 Mcfgpd, 24/64" ck. 48/5374-86 (Morr) tbg 5393,

1-84W 2  
SHEET NO.

STATE Kans COUNTY Clark SEC. 16 TWP. 33S MAP NO. 21W RGE.

OPERATOR Ashland Oil & Refining Co loc. App SW NE SW

WELL NO. 1 FARM NAME Folks Unit

500# Rock salt, 500MA, Ga 1336 Mcfgpd, 16/64" ck,  
Ga 3,459 Mcfgpd + 14 B Dist /16 hrs, 4 Pt OF: 37,000  
Mcfgpd (Commingle) Morr & Chest 5374-5430.

COMPLETED

51P 1566

OPERATOR Ashland Oil & Refining

WELL NO. 1 Folks Unit