

KANSAS DRILLERS LOG

API No. 15 — 033 — 20248
County Number

Operator

Texas Oil & Gas

Address

Suite 300 200 W. Douglas Wichita, Ks 67202

Well No.

#1

Lease Name

Einsel "D"

Footage Location

330 feet from (N) (S) line 2310 feet from (E) (W) line

Principal Contractor

Xplor Drlg. Co.

Geologist

High Plains Consulting, Ltd.

Spud Date

4-21-78

Total Depth

5122'

P.B.T.D.

N/A

Date Completed

6-02-78

Oil Purchaser

N/A


S. 12 T. 33S R. 17W

Loc. 330' FNL 2310' FWL

County Comanche

640 Acres

N



Locate well correctly

Elev.: Gr. 1947'

DF 1952' KB 1955'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	24#	614'	Lite-weight Common	400 150	3% CaCl, 2% Gel
Production		4 1/2"	10.5#	5083'	50/50 Pozmix	150	18% NaCl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A			
TUBING RECORD			N/A	N/A	N/A
Size	Setting depth	Packer set at			
2-3/8"	5060'	N/A			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
10,000 gal. acid; 9000# sand; 10,000 gal. wtr.	O.H. 5083-5120'

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
Shut-in	Flowing				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	N/A bbls.	476 MCF	53 bbls.	N/A	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
Shut-in			O. H. 5083-5120' (Miss)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Texas Oil & Gas Corp.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

1

Lease Name

Einsel "D"

Gas Well

S 12 T 33S R 17 E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Heebner	4214	-2259		
Douglas	4274	-2319		
Lansing	4434	-2479		
Swope	4789	-2834		
Hertha	4841	-2886		
Mississippi	5080	-3125		
TD	5122	-3167		
DST #1, 5088-5122', (Mississippi) w/results as follows: IFP/30": 133-133#, severe plugging ISIP/60": 788# FFP/90": 122-122#, GTS/14", gauged 196 MCFD FSIP/135": 594# Rec 293' DM.				
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received

HAROLD A. BROWN
District Geologist

Signature

Title

June 2, 1978

Date

Geological Survey

WICHITA BRANCH

WELL LOG

15-033-20248
12-33-17W

EINSEL D #1
330' FNL 2310' FWL
Section 12-33S-17W
Commanche County, Kansas

OPERATOR: TEXAS OIL AND GAS CORP.
CONTRACTOR: XPLOR DRILLING CO.

COMMENCED: 4-21-78
COMPLETED: 4-30-78

CASING RECORD: Ran 15 jts. 8 5/8" surface casing, set @ 614', new 24#.
 Cement with 550 sacks cement, 400 sacks Light Weight, 150
 sacks Class H, 3% cal.chloride 2% gel.
 Ran 156 jts. production casing, set @5083', new 10.5#.
 Cement with 150 sacks 50/50 posmix, 18% NACL 1.25# CRF 2
 8# gilsonite per sack.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Sand & Red Bed	0	625	1947 Gr.
Red Bed	625	2030	1952 D.F.
Lime & Shale	2030	5122	1955 K.B.
R.T.D.	5122		

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

RECEIVED
MAY 03 1978
DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the Driller's Log of the
well drilled 330' FNL & 2310' FWL of Section 12-33S-17W, Commanche County, Kansas,
to the best of my knowledge and belief.

XPLOR DRILLING CO.

Kirby C. Evers

Kirby C. Evers, Vice President

Subscribed and sworn to before me this 2nd. day of May, 1978.

MY COMMISSION EXPIRES:
August 25, 1980

Virginia Lee Smith

Virginia Lee Smith, Notary Public