

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

13-33-17W

COMPANY J. M. HUBER CORP

SEC. 13 T. 33 R. 17W

FARM Einsel-Biddle NO. 3

LOC. C SW

TOTAL DEPTH 5165
3156'

COUNTY Comanche


COMM. 10-16-67

COMP. 10-29-67

SHOT OR TREATED

CONTRACTOR Leben Drilling

ISSUED 12-2-67



CASING

20	10	
15	8 5/8" 412'	cem w/ 300 sx
12	6	
13	5	

ELEVATION 1894' KB

PRODUCTION DRY/MISS

FIGURES INDICATE BOTTOM OF FORMATIONS

0	365	Redbed	TOPS: LOG
365	1160	Redbed, Shale	Heebner 4170
1160	1500	Shale	Lansing 4360
1500	2137	Shale, Shells	Base Kansas City 4788
2137	2428	Lime	Marmaton 4806
2428	2645	Lime, Shale	Cherokee 4985
2645	3090	Lime	Mississippi 5045
3090	4330	Lime, Shale	
4330	5165	Lime	
	5165	RTD - D. & A.	

8 5/8" new 24# surface casing set @ 412' cemented with 300 sacks of Posmix, 2% gel, 2% cc, + 100 sks. Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Einsel-Biddle #3 Well, located C SW of Section 13, Township 33 South, Range 17 West, Comanche County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
COUNTY OF BARTON) SS