

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

14-33-17W

COMPANY CONTINENTAL OIL

SEC. 14 T. 33 R. 17W
 LOC. C N/2 NW

FARM C. Einsel Gas Unit NO. 1

TOTAL DEPTH 5230

COUNTY Comanche


COMM. 4-3-66

COMP. 4-22-66

SHOT OR TREATED

CONTRACTOR Leben Drlg,

ISSUED 4-29-67



CASING 1 3/8" @ 398' w/325 SX

20 10

15 8

12 6

13 5 1/2" @ 5230' w/350 SX

ELEVATION 1925' KB

PRODUCTION SWDW-Rate
 Satisfactory (LANS
 4435-55)

FIGURES INDICATE BOTTOM OF FORMATIONS

0	90	Shale, Redbed
90	110	Sand
110	1370	Redbed
1370	1500	Anhydrite, Shale
1500	1771	Shale, Lime
1771	2000	Shale, Shells
2000	2460	Shale, Lime
2460	3410	Lime, Shale
3410	3560	Shale, Shells
3560	3874	Shale, Lime
3874	4230	Lime, Shale
4230	4344	Sandy Shale, Lime
4344	4440	Lime, Shale
4440	5025	Lime
5025	5058	Lime, Shale
5058	5106	Lime
5106	5143	Shale, Lime
5143	5169	Lime, Chert
5169	5190	Lime
5190	5230	Lime, Chert
	<u>5230</u>	<u>RTD - Set 5 1/2" Casing</u>

Set 13 3/8" new spiral weld casing @ 398' with 325 sacks Common, 2% Gel, 2% cc

TOPS: SCOUT

Heebner	4194
Douglas	4251
Lansing	4390
Base Kansas City	4875
Marmaton	4890
Cherokee	5020
Mississippi Warsaw	5084
Mississippi Osage	5188