

P1

**IMPORTANT**  
Kans. Geo. Survey request  
samples on this well.

**KANSAS DRILLERS LOG**

API No. 15 — 033 — 20,346  
County Number

Operator  
Griggs Oil, Inc.

Address  
1625 Vickers KSB&T Building Wichita, Kansas 67203

Well No. #1 Lease Name Einsel #B

Footage Location  
1650 feet from (N) (X) line 330 feet from (E) (X) line

Principal Contractor Venture Drilling Geologist Louis S. Bird

Spud Date 4/10/80 Total Depth 5099 P.B.T.D. ---


Date Completed 5/20/80 Oil Purchaser Clear Creek

S. 14 T. 33 R. 17 E/W

Loc. NE SE NW

County Comanche

640 Acres  
N



Locate well correctly

Elev.: Gr. 1893

DF 1903 KB 1906

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	12 1/4	8 5/8	28	474	Common	250	2% gel 3% cc
production	7 7/8	5 1/2	15 1/2	5093	Halliburton light 60/40 poz mix	50 150	18% salt

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
none			none		

**TUBING RECORD**

Size	Setting depth	Packer set at
2 7/8	5070	none

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
500 regular Az	5093-99

**INITIAL PRODUCTION**

Date of first production <u>6/13/80</u>	Producing method (flowing, pumping, gas lift, etc.) <u>pumping</u>
RATE OF PRODUCTION PER 24 HOURS	Oil <u>65</u> bbls. Gas <u>TSTM</u> MCF Water <u>0</u> bbls. Gas-oil ratio <u>---</u> CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval(s) <u>5093-99</u>

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Griggs Oil Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,  
DRY HOLE, SWDW, ETC.:  
oil

Well No.

B #1

Lease Name

Einsel

S 14 T 33 R 17 W

### WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

Mississippi

5070

5099

Heebner

4188

LKC

4412

DST #1, 5092 -99, 30/60/60/90

Stark Sh

4718

GTS 13", 29 MCF, Recovered

Swope

4730

885' Oil, 34° API

Base LKC

4812

SIP 1684/1653

Ft. Scott

4998

Flow Pressure 42/127 - 191/309

Cherokee Sh

5007

Mississippi

5070

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Title

Date

*J.M. Hatcher*  
FNGR  
9/8/80