

**IMPORTANT**  
 Kans. Geo. Survey request  
 samples on this well.

15-033-20279

**KANSAS DRILLERS LOG**


S. 29 T. 33 R. 17 <sup>E</sup>W

API No. 15 — 033 — 20,279  
 County Number

Loc. C SE

County Comanche

640 Acres  
N



Locate well correctly

Elev.: Gr. 1827

DF \_\_\_\_\_ KB 1832

Operator  
Mid-Continent Energy Corp.

Address 712 One Twenty Building Wichita, Kansas 67202

Well No. #1 Lease Name Jobe

Footage Location  
1320 feet from (N) (S) line 1320 feet from (E) (W) line

Principal Contractor Slawson Drilling Co. Geologist \_\_\_\_\_

Spud Date Feb. 19, 1979 Total Depth 5170' P.B.T.D. \_\_\_\_\_

Date Completed March 7, 1979 Oil Purchaser N/A

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	20#	446'	Halco Light Class A	250 150 + 75	3% cc & 1/2# flocele 3%

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A			
<b>TUBING RECORD</b>			N/A		
Size	Setting depth	Packer set at			
N/A	N/A	N/A			

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
N/A	

**INITIAL PRODUCTION**

Date of first production N/A		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

**INSTRUCTIONS:** As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Well No. 1 Lease Name Jobe Dry Hole

S 29 T 33S R 17 W


**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Chase Group	2376	544		
Council Grove Group	2762	930		
Wabaunsee Group	3282	1450		
Stotler	3392	1560		
Base/Lecompton	4000	2168		
Heebner	4191	2359		
Lansing	4384	2552		
Swope	4800	2968		
B/KC	4876	3044		
Altamont	4934	3102		
Pawnee	4980	3148		
Cherokee	5023	3191		
Mississippi	5095	3263		
RTD	5170			
<u>DST #1</u> (Mississippi) MISRUN	4988-5105			
<u>DST #2</u> (Mississippi) 30-60-45-90	4988-5105			
ISIP 1383				
IFP 141-141 Strong blow				
FSIP 1635				
FFP 161-172 Strong blow				
Rec: 3520' GIP, 211' SGCM, 2' WTRYM, 62' MDYWTR				
<u>DST #3</u> (Mississippi) 30-60-45-90	5103-5130'			
ISIP 70				
IFP 70-70 Strong blow after 10 min.				
FSIP 70				
FFP 70-70 Fair to good blow				
Rec: 22' Gas, 102' DM.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Signature Rodney E. Andersen, Geological Manager Title April 2, 1979 Date
---------------	---