


14-33s-17w

15-033-21551-0000


TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Redland Resources Inc.

Einsel #14-11

6001 NW 23rd Street
Oklahoma City Ok. 73127

14 33 17 Comanche KS

Job Ticket: 35061

DST#: 1

ATTN: David Hickman

Test Start: 2009.04.25 @ 20:20:05

GENERAL INFORMATION:

Formation: **Miss.**Deviated: **No** Whipstock: **ft (KB)**

Time Tool Opened: 22:46:05

Time Test Ended: 05:21:50

Test Type: Conventional Straddle

Tester: Gary Pevoteaux

Unit No: 39

Interval: **5084.00 ft (KB) To 5115.00 ft (KB) (TVD)**Total Depth: **5246.00 ft (KB) (TVD)**Hole Diameter: **7.88 inches** Hole Condition: **Fair**Reference Elevations: **1905.00 ft (KB)****1892.00 ft (CF)**KB to GR/CF: **13.00 ft**Serial #: **8167**

Inside

Press@RunDepth: **37.74 psig @ 5085.00 ft (KB)**Start Date: **2009.04.25**

End Date:

2009.04.26Capacity: **7000.00 psig**Last Calib.: **2009.04.26**Start Time: **20:20:10**

End Time:

05:21:50Time On Btm: **2009.04.25 @ 22:43:35**Time Off Btm: **2009.04.26 @ 02:22:04**


TEST COMMENT: IF:Weak blow . 1/2 - 1".

IS:No blow .

FF:Weak blow . 1/4".

FS:No blow .

Pressure vs. Time



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2559.79	119.48	Initial Hydro-static
3	21.50	118.97	Open To Flow (1)
31	25.27	120.14	Shut-In (1)
93	236.38	121.77	End Shut-In (1)
93	28.96	121.71	Open To Flow (2)
125	37.74	122.32	Shut-In (2)
218	490.87	123.66	End Shut-In (2)
219	2599.97	124.63	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
25.00	Drig. mud	0.12

Gas Rates


	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------

RECEIVED

JUN 18 2009

KCC WICHITA

14-33s-17w
SW NE NE GW



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

Redland Resources Inc.

Einsel #14-11

6001 NW 23rd Street
Oklahoma City Ok.73127

14 33 17 Comanche KS

Job Ticket: 35061

DST#: 1

ATTN: David Hickman

Test Start: 2009.04.25 @ 20:20:05

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

4000 ppm

Viscosity: 53.00 sec/qt

Cushion Volume:

bbl

Water Loss: 6.80 in³

Gas Cushion Type:

Resistivity: 0.00 ohm.m

Gas Cushion Pressure:

psig

Salinity: 4000.00 ppm

Filter Cake: 0.20 inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
25.00	Drig.mud	0.123

Total Length: 25.00 ft

Total Volume: 0.123 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #: none

Laboratory Name:

Laboratory Location:

Recovery Comments: Sampler Data:3090 ML mud, LCM, & a trace of gas @ 74 psi.

Pressure vs. Time

