


9-247W

Map No. *K-84*

OPER CABOT CORPORATION
PAMPA, TEXAS
 WELL #1 ELIZABETH BRILL
WAKEFIELD DRLG.
 FIELD EVALYN-CONDIT FIELD (MAR, MRW, MISS)
 I.P. GA 20,000,000 CFGPD MRW 5656-70



S-T-R 17-33S-33W
 SPOT APP C NE
 CO SEWARD, KS. ✓
 ELEV 2859 KB

KB LOG:
 MRW 5628- 2769
 MRW SD 5654- 2795
 B/MRW SD 5672- 2813
 CHEST 5894- 3035
 CHEST SD 6144- 3285
 ST G 6202- 3343
 ST L 6322- 3463
 LTD 6400- 3541

GEOL - JOHN ROSS

SPD 8-16-66 8-5/8" @1636/875 SX
 DST #1 (MRW) 5628-5712, OP 15", GTS 1½", GA 6,240,000CFGPD
 2", GA 9,972,000 CFGPD/5", R 2' DIST, ISIP 1634#/30",
 FP'S 1541-1590#, FSIP 1634#/30"

(NO UP HOLE TOPS CALLED)

DST #2 (MRW) 5856-5900 FAIL
 DST #3 (MRW) 5865-5900, OP 70", R 35' M, ISIP 449#/30",
 FP'S 195-242#, FSIP 289#/30"
 DST #4 (CHEST) 6106-18, OP 55", R 5' M, ISIP 124#/30",
 FP'S 10-12#, FSIP 37#/30"
 DST #5 (CHEST) 6152-72, OP 2¼ HR, 200' GIP, R 35' SLI OCM,
 ISIP 61#/45", FP'S 1515#, FSIP 92#/60"

Data Inc

SEWARD CABOT CORPORATION
 17-33S-33W #1 ELIZABETH BRILL
 APP C NE/4

SPL:
 MRW 5634
 MRW SD 5658
 B/" SD 5674
 MRW SD 5859
 B/" SD 5873
 MRW SD 5885
 B/" SD 5890

DST #6 (ST L) 6305-6400, OP 42", R 15' M, NO SHO, ISIP
 936#/30", FP'S 0-0#, FSIP 110#/30"
 RTD 6400, WELEX LOG, 4½" 5800 W/250 SX
 CO 5684' PE 28/5656-70 (MRW) 1½" TBG @5652, 1000 A,
 (15%) § LD, FLOW GA 20,000,000 CFGPD, SICP 1550#/8 HRS,
 SITP 1530#/8 HRS, MRW 5656-70 COMPLETED 9-23-66

MISCEL DATA

GEOL JOHN ROSS
 FTG 1390' FNL & 1250' FEL
 SUPPT _____
 CSG 8" 1636/875 SX 4½" 5800/250 SX

2-S 2854 DF
 ELEV 2856 DF

SPUD DATE 8-16-66
 DRLG COMP _____
 FR by DATA 8-8-66
 COMP by " 9-29-66