

WC *

4

Field

State KansasCounty MeadeCompany Shamrock Oil Co.Farm W. W. LanghoferWell No. 1Sec. 18 Twp. 33S Range 30W

fr N

fr E

fr S

fr W

of NW SEContractor Cree Only.

Remarks

Comm. 6-21-55 Comp. 9-7-55Elev. 2738 T. D. 5692 P. B.Pay 5654-59 - 5661-73I. P. 9,000 mcf R. P. 1894 #Casing Record: 13 3/8 638/500 720 10 3/4 51 1/2 5693/30016 8 5/8 2630/800

6-15-55 LOC

Tops

Delo. 2600

JUN 22 1955

Ø 215Lang 4496

JUN 29 1955

Ø 2491Mamm 5124

JUL 6 1955

9 5/8 @ 2630/800Mon sd. 5604DST 3108-3147 op 70 minMISS 5661wh blo mtr to gdn 5 minrev 90' dm, 660' SW FP 55-400BN 715/30 NH 1450Ø 3232

JUL 13 1955

Ø 4730

JUL 20 1955

DST 4990-90 op 1 hr. 33 minwh blo, rev 625' SW, 15' dmFP 35-320, BN 1540/30 NH 2635Ø @ 5615-5657. rev 42' g sd, sh 4 dm.btm 4 1/2' g d sd w/ndow floor, strprep to DST 5600-5657

45615-57 rec 42'

8" gm wry sh.

3'4" tite lm w/ spotted plum & cut, sh. odor

1'6" sh.

6" fm - crs foss lm. w/ spotted plum & cut

sh. odor.

1' brn fm - crs, vug, sat. lm w/ h. vert frant.

1' lt. brn fm. tite argill. sd. w/ the pp por

spotted plum, cut, gd vdm, th. bleed out

4" brn, tite, sat sd

7" sh.

6" brn fm tite sat. sd.

3'6" gm, v glauc, argill. sd.

2' fm - crs plw tite glauc, foss. lm.

1' fm - tite, glauc, calc. sd

1' gm, glauc. glauc. sd. w/ spotted plum,

cut, th. bleeding oil, sh. odor.

1' blk sh. w/ striae fm sd sat sat sd.

1' dark gm, sdig sh.

1' sh. & tite sd.

2'6" blk rotten sh.

6" buff fm sd w/ fr. str, plum, cut, odor

w/ to of por

1' as above w/ fr - gd por.

3' glauc, sat fm. sd w/ gd por, plum,

odor, vert frant.

DST 5600-57 of 1 hr. 10 min GTS in 5 min

g - 4410 msp in 10 min

1, 587 " " 15 "

1, 893 " " 45 "

1, 930 " " 1 hr. rec 5' mud

FP 265-315, BH 1895/20 1/4 H 7840

45657-72 rec 13.3'

1' buff fm, glauc, v por. sd w/ sat. str.

plum, cut, odor

1' brn. fm - crs glauc v unidul lm w/

foss blk sh striae, scattered str & plum

1' blk. sh.

Field-----

State _____ County _____

County-----

Company _____

Farm _____ Well No. _____

Well No.

Sec.	Twp. Blk.	Range Survey	Well No.
------	--------------	-----------------	----------

Sec.	Twp.	Range	
-----	Blk.	Survey	-----

fr N fr E fr S fr W

of 0 later

Contractor Tangray

Remarks W. A. S. J.

Comm. _____ Comp. _____

Elev. _____ T. D. _____ P. B. _____

Pay -----

I. P. _____ R. P. _____

Casing Record: 13 3/8----- 7-----

20 ----- 10 3/4 ----- 5 1/2 -----

16 _____ $8 \frac{5}{8}$ _____

Tops

~~AUG 31 1955~~

✓ absolute OF
9000 m
STP 1603 #
STBNP 1894 #

SEP 7 1955

Schl

Kr. 2627

Wing 2727

U F & Pil 2794

L " " 2874

Flower 2926

C.G. 3097

Shawnee 4304

Sang 4483

Mahm 5108

Cik 5275

Atoka 5391

more ad. 5608

Cher 5663

¢