

WELL COMPLETION REPORT AND
DRILLER'S LOGState Geological Survey
WICHITA BRANCHAPI No. 15 — 033 — 20,493
County Number

Operator

Lear Petroleum Exploration, Inc.

Address

6401 NW Grand Blvd. Suite 200 Oklahoma City, Oklahoma 73116

Well No.

4-5

Lease Name

JELLISON

Footage Location

2310

feet from (S) line

2310

feet from (E) line

Principal Contractor

Husky Drilling Company

Geologist

Lou Bird

Spud Date

8-24-81

Date Completed

9-15-81

Total Depth

5300'

P.B.T.D.

5246'

Directional Deviation

3/4° @ 5300'

Oil and/or Gas Purchaser


Koch

S. 5 T. 33S R. 19 E
W

Loc. C NW NE

County Comanche

640 Acres



Locate well correctly

Elev.: Gr. 1883'

DF 1891' KB 1892'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	24#	665'	Lite Common	300	Gel/CC/Celo
			11.6#		Class H	50	Gil
Production	7-7/8"	4 1/2"	9.5 & 10.5	5300'	50/50 Poz	200	Salt/Gil

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1	.39" Jet	5068-5213'
TUBING RECORD					
Size	Setting depth	Packer set at			
2-3/8"	5193'	N/A			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/2000 gals HNE acid.	5068-5213'

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
10-21-81	Pumping				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	25 bbls.	130 MCF	180 bbls.	5200	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
Sold-Michigan-Wisconsin			Mississippi		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Oil

Well No.

Lease Name
JELLISON

4-5

S 5 T 33S R 19 ¹/_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Heebner	4158'			
Lansing	4334'			
Stark	4748'			
BKC	4836'		GRN	5251-3600'
Marmaton	4852'			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____

R Stanley DeLong
Signature

Signature

Division Production Engineer

Title

November 2, 1981

Date _____