

10-285W MAP NO. (OWWO) SEC. 19-33S-21W
 STATE Kans COUNTY Clark LOC. C NW/4
 OPER Graham-Michaelis Drilling Co. FT/FR LINE
 WELL 1-19 FARM McMinimy (OWWO) FT/FR LINE
 POOL Sitka Ext ELEV 1894 0 DF 1897 0 KB
 CONT. Co. tools GEOL.
 CO. 5475' Gas Test
 INT.
 F.R. 7-26-63 SPUD 10-22-63
 TD 5474 FM. St Gen COMP. 5410
 P.BTD.

Completion Record	PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
	Chester	5356-64	32	500A & Frac	
	I.P. Cal OF: 875,000 Cfgpd (No SIP)				

Casing Record	
	13 3/8" @40 w/cem, 7" @2465 w/900 sx.,
	4 1/2" @5474 w/100 sx.

Data Inc.

(KB Log - Old)	B/Ches sd	5314	-3417
Lans 4428 -2531	Sdy 1m	5358	-3461
Marm 4996 -3099	St Gen	5384	-3487
Cher gr 5125 -3228	RTD	5402	-3505
Morr 5270 -3373	LTD	5403	-3506
Mor sd 5290 -3393	New Info:		
Ches sd 5308 -3411	DDTD	5474	-3577

OLD INFO (Was John P. Booth #1 McMinimy "B") - Patton Drlg., Spud 9-15-61, lost circ @1545, RTD 5402, No DST's, D&A 10-9-61
 NEW INFO: Graham Michaelis MIRT, CO & DD 5474 TD, 4 1/2" @5474 w/ 100 sx., MICT (8-15-63) Perf 40/5358-68, 24/5390-96 (Chest), 1500A, Frac 30,000# sd x 30,000 Gal flu, Ga 1,500,000 Cfgpd/NT, Sq 5358-96 w/300 sx., CO 5410, P.BTD, Re Perf 32/5356-64 (Chest), 500A + frac 15000# sd x 15000 GW, Rec Id, Cal OF 875,000 Cfgpd - No SIP avail, Chest 5356-64 - COMPLETED
 CORRECTION (8-7-63) Was New Well - Is OWWO