


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CARTER OIL COMPANY
Farm - Dowis No. 2

SEC. 12 T. 33 R. 2W
CNW SW

Total Depth. 4236'
Comm. 8-5-47 Comp. 9-13-47
Shot or Treated.
Contractor. Earl F. Wakefield
Issued. 1-10-48

County. Sumner
KANSAS



Elevation. 1220 *sch*

CASING:
8-5/8" 547' Cem.
5-1/2" 4231' Cem.

Production. Drawdown Pot. 1829
BO, no wtr.

Figures Indicate Bottom of Formations.

surface clay & sand	50
clay & sand	75
shale shell streaks	318
shells shale	355
salt	390
lime	435
lime shale	450
lime broken	468
shale	488
lime broken	547
lime shale	935
lime broken & shale	1200
lime shale	1514
shale shells	1752
lime	1782
shale lime shells strks	1905
shale shells	1930
lime	1950
lime shale	2001
shale	2085
lime	2222
lime shale	2260
shale sand lime	2320
lime	2348
lime broken	2500
lime shale sand strks	2537
lime shale	2625
lime	2660
shale	2740
shale shells	2780
lime shale	2856
shale	2908
sand	2958
shale shells	2973
lime brown	2996
lime broken, shale	3045
shale	3200
shale shell	3227
K. C. lime	3255
lime	3353
broken lime shale	3393
shale & lime strks	3495
shale	3508
shale lime	3605
lime shale strks	3757
lime & shale	3876
Mississippi lime	3916
lime	4026
lime cherty	4067
lime	4165
shale & lime	4228
shale	4230
sand	4236

TOPS:
 Cherokee 3758
 Mississippi 3876
 Kinderhook 4165
 Simpson 4231

Initial Production - 384 bbls.
 per day, no wtr 19/64" choke
 (7 1/2 hr. flow test) Gas oil
 ratio = 600 cu ft./bbl.
 Initial Pot. - 1829 BO, no wtr.
 (Drawdown) Taken 9-19-47.

CABLE TOOL INFORMATION

Bailed mud
 Drilled TD 4216' - cement
 Loaded hole with water
 Drilled plug & shoe &
 cleaned out to Rotary
 Total Depth of 4236'
 Ran 2" sue tbg. & swabbed
 (well kicked off)

Total Depth

Ran Schlumberger Test @ 4235'