

Field Leslie Pool
State Kansas County Meade

Company Colorado Oil & Gas Co.

Farm Holmes Well No. 5

Sec. 2 Twp. 33S Range 30W
Blk. 33S Survey 30W

fr N. fr E. fr S. fr W

of C NW SE

Contractor NYE & SWEET

Remarks

Comm. 5/6/56 Comp. 7/11/56

Elev. 2728 OF. T. D. 5882 P. B.

Pay Temporarily Abandoned

I. P. R. P.

Casing Record: 13 3/8 7

20 10 3/4 5 1/2 5870/200

16 8 5/8 604/700

	LOG	Tops	
			<u>Log 4558 - 4560</u>
MAY 9	<u>fishy @ 583</u>		<u>Nov 5680 - 5674</u>
MAY 16	<u>plug hole checked</u>		<u>SD 5734 - 5734</u>
	<u>Rig 16' West. spds 1/10/56</u>		<u>MISS 5760 - 5760</u>
TTD	<u>2679 lost concn.</u>		<u>Nov 5124</u>
MAY 23	<u>ret fish T.O. 3637</u>		<u>CRK 5342</u>
	<u>fishy @ 4100</u>		<u>ATOKA 5500</u>
MAY 30	<u>φ 5240</u>		
JUN 8	<u>DST 5757-90-092 hie.</u>		
	<u>sp 100 T.O. Dec 100' OCM.</u>		
	<u>FP 25-F75 SIP 510/30</u>		
	<u>RTD 5882 TAN Log</u>		
	<u>Set 5 1/2 @ 5870/200</u>		
	<u>MILT.</u>		
JUN 13	<u>CO to 5843 now RA log of 28/5778</u>		
	<u>85-1184/5791-5837 snatched 5 li 5 ho</u>		
	<u>sp. A/10,000 snatched 8 BOPH for 6 hie</u>		
	<u>snatched 4 BO + 4 BAW ph for 2 hie 5 li</u>		
	<u>also sp. at end 4 BOPH + .2% water</u>		
	<u>prep to frac</u>		

JUN 30

~~frac/500 A.7. 600 frac/6000~~
~~sd/1500 frac/13,000 sd/6500 400/A~~
~~A/1500 7.5% W/5600 - subbed 23~~
~~bbls oil + 56 w in 6 hrs. hd 50'~~
~~sd in reg CO. subbed 4 BOPH~~
~~for evn 21% water. - subbed AVG~~
~~2.5 bbls fluid per 22% water.~~
~~subbed 2 BOPH. gas T.S.T.M. -~~
~~set pl @ 5770 of 28/5740-47 16/5753~~
~~-57 aptal 250g A subbed 5 bbls~~
~~fluid per hr 35% w) common w chest?~~

JUN 27

~~sub 2.25 bbl fluid per hr.~~
~~78% oil. 22% AW. dec to 1 bbl ph.~~
~~gel bloc 1000 gal frac/10,000 sd/5000.~~
~~Crude/6000 ~~frac~~ sub. ag 5740-47 +~~
~~5753-57 w 50 out. CO to 5770 of~~
~~28/5740-47 16/5753-57 - A/250 Crude~~
~~2600 frac/2250 frac/8000 sd/2000 frac/3000~~
~~sd/2250 frac/1500 sd/2250 Crude/6000~~
~~submitting load from TD 5843~~

JUL 5

~~8 bbls load pt. for 8 hrs dec to 1 bbl~~
~~ph. - pl to bottom. subbed 13 bbls~~
~~load avg 1.2 bbls load per hr.~~
~~have 194 bbls load left.~~

JUL 11

~~bailed 40 gal A residue + 209 gph~~
~~Temporarily Abandoned.~~

AMARILLO TOPS

- 2720 GL
- Winfield 2816 (-96)
- Heebner 4430 (-1710)
- Lansing 4560 (-1840)
- Marmaton 5196 (-2476)
- Morrow 5680 (-2960)
- Morrow sd 5734 (-3014) T 22', por 6', SO
- Chester 5760 (-3040)
- TD 5874 (-3154)