

WILDCAT

8-148W Map No. 284
 OPER AMARILLO NAT. GAS CO. & W.J. FELLERS
AMARILLO, TEXAS

WELL # 1 HEADRICK

MAHONEY DRLG.

WC 1 MI S OF MASSONI FIELD (MULTI PAY)I.P. P 84 BOPD + TR WTR, GR 28, ST L 5903½-07½DISCOVERY OF MASSONI EAST FIELD (MISS OIL)

SPD 6-29-66 8" @1299/700 SX DOUGLAS MARDEN, GEOL

(MASSONI EAST DISCOVERY (MISS OIL))

DST #1 (MAR) 5095-5140, OP 70", GTS/3", GA 1,000,000 CFG
 PD, GA 1,800,000 CFGPD/15", GA 650,000 CFGPD/70", R 100'
 VHO&GCM + 60'HOCSW + 170'OCSW, ISIP 524#/30", FP 215-
 108#, FSIP 987#/30"

RTD 5975' (RNG LOG) 4" @5974/175 SX

MICT, PF 16/5903½-07½ (ST L) 500MCA, 8 2 BOPH + SG
 NT, 3000 CRA, 8 LD, 8 5 BOPH, NW + 300,000 CFGPD, NT

FLO 3½ BOPH, NW, NT(15/64"CK)POP STATE POT: P 84 BOPD
+ TR WTR (GR 28 DEG) ST LOUIS 5903½-07½ COMPLETED 8-16-66

(DISC OF MASSONI EAST FIELD (MISS OIL))

S-T-R 2-33S-31WSPOT C NE SWCO SEWARD (KS)ELEV 2781 KB

KB LOG:

HB 4268 -1487
 U/TOR 4304 -1523
 L/TOR 4349 -1568
 LAN 4416 -1635
 MAR 5039 -2258
 MRW 5521 -2740
 CHEST 5580 -2799
 STE G 5760 -2979
 ST L 5837 -3056
 LTD 5976 -3195
 RTD 5975 -3194

SPLS (KB)

LAN 4413-1632
 MAR 5037-2256
 MRW 5529-2748
 CHEST 5581-2800
 STE G 5779-2998
 ST L 5850-3069
 RTD 5975-3194

Data Inc

MISCEL DATA

GEOL DOUG MARDENFTG 284

SUPPT

CSG 8" 1299 W/700 SX. 4" 5974 W/175 SX.ELEV 2778 DF 25

2771 GR

SPUD DATE 6-29-66

DRLG COMP

FR by DATA 6-30-66COMP by " 8-18-66