

12-350W+

MAP NO.

84

SEC.

20-33S-30W

STATE Kans

COUNTY

Meade

LOC.

C NE NW

OPER. W. J. Coppinger

FT/FR

LINE

WELL 1 FARM Meyer

FT/FR

LINE

POOL Bruno (Confirmation)

ELEV 2714

GR.

2722

DF

2724

KB

D & M Drlg. Co.

GEOL. Doug M. Marden

CONT. (6200' Oil Tst)

F.R. 11/7/62

SPUD

11/8/62

COMP.

12/26/62

TD. 6228

FM.

St Louis

PBT.


PRODUCING FM.

FROM

TO

PERF. W/HOLES

TREATMENT

COMPLETION RECORD
PROD. INTERVAL
& TREATMENT

Data Inc.

D & ACASING
RECORD

SIZE

DEPTH

SAX

SIZE

DEPTH

SAX

8 5/8" @

1458'

w/625

4 1/2" @

5800'

w/125

OPER. W. J. Coppinger

SEC.

20-33S-30W

WELL 1 Meyer

ELEV

2724 KB

LOC.

C NE NW

(KB) Sp1

(KB) Log

Tor 4376

C.G. 2976 - 252

KC 4506

Adm 3292 - 568

Marm 5126

Waub 3474 - 750

Morr 5642

Shaw 3870 -1146

Chest 5703

Hb 4352 -1628

Ste Gen 5980

Tor 4387 -1663

St Lou 6148

Lm 4506 -1782

RTD 6225

Marm 5132 -2408

Ø #1 (Morr) 5652-5712', R 12' Sds Chero 5300 -2576

w/SO, 6' Sds w/SO, 1' Blk sh, Atoka 5482 -2758

7' Sds, 10' Fn Gr Sds w/Sh Morr 5642 -2918

Stringers, 9' Sds w/SO, 6' Grn Chest 5706 -2982

Sds, NS. Ste Gen 5974 -3250

DST #1 (Chest) 5703-12', Op 1 hr, St Lou 6142 -3418

R 20' GSM, IBHP 20#/30", IFP LTD (St Lou) 6228 -3504

20#, FFP 20#, FBHP 20#/30".

DST #2 (Morr-Chest) 5666-5712', Op 1 hr, R 115' GCM w/Few Spks

Oil, IBHP 130#/30", IFP 95#, FFP 95#, FBHP 120#/30".

DST #3 (Morr) 5654-67' (Str Pkr), Op 1½ hrs, GTS/3", R 180' GCM

+ 3620' GXW, FP 880-2110, BHP 2110-2110/20:
DST #4 (Chest) 5942-63 (SP), op 1 hr, rec 5' M, FP 8-8,
BHP 8-8/30 mins.

RTD 6225 (Miss, Sj log, 4 $\frac{1}{2}$ " @ 5800/150 sx, CO, Hydra-Jet
notch @ 5696 $\frac{1}{2}$ (Mor), A/500 M, \$ 1/3 BOPH/6 hrs w/sho gas, sd
oil frac/18,300 gal oil x sd/8226# x 580# walnut hulls,
rec 202 BL/20 hrs, \$ 6 BFPH/8 hrs (45% wtr) + 1,000 MCFPD,
WHSIP 300#, FU 30 BW + 1 BO/12 hrs, flo 12 BF/2 hrs, (90%
wtr). D & A. 12/15/62.

LIBERAL ELECTRIC LOG TOPS

2724 KB

Winfield 2742 (-18)

Heebner 4366 (-1642)

Toronto 4388 (-1664)

Lansing 4505 (-1781)

Marmaton 5132 (-2408)

Morrow 5642 (-2918)

"S-2" Sand 5650 (-2926) 31/50; Cored; \$ 12 BFl/2' (90% W)

Chester 5746 (-3022) tst 5' mud

Ste. Gen 5974 (-3250)

St. Louis 6136 (-3412)

TD 6225 D & A