

10-53
MAP NO.STATE Kans COUNTY Seward SEC. 20 TWP. 33S RGE. 31WOPERATOR Cabot Carbon LOC. C SW/4WELL NO. 1 FARM NAME Floyd Massoni "B" FT. FROM _____ LINED1 WC FT. FROM _____ LINEFR. 8/17/60 SPUD 8/9/60 COMP. 10/6/60CONT./GEOL. Midwestern Drlg. Tools.

COMPLETION RECORD

NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD

a Chest 5770-76 24 500 MAb Chest 5784-96 40 20,000 A 15%

c _____

d _____

a I. P. OIL/DIST. _____ WTR. _____ GAS _____ M.C.F.P.D. _____ CHK. _____ HRS. _____

b " " " " " "

c " " " " " "

d 12 hr BD 2000 MCFGPD.SICP 1550# 36 hr. SITP 1700#. D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBDT _____ TD 6330

CASING - CEMENT RECORD

SIZE DEPTH W/SAX. SIZE DEPTH W/SAX.

8" 2308 750 _____5 1/2" 5906 350 _____OPERATOR Cabot Carbon WELL NO. 1 Floyd Massoni "B" ELEV. 2729 DF

SAMPLE TOPS DEPTH SUB SEA ELEC. TOPS DEPTH SUB SEA

Anardarko (DHM) _____ Herr 2587 _____Gulf (DHM) _____ Kri 2620 __________ CG 2956 __________ B Heeb 4308 __________ Tor 4341 __________ LKC 4445 -1715 __________ DesM 5120 -2390 __________ Cher 5288 __________ Morr 5646 -2916 __________ Che 5750 -3020 __________ St G 6036 -3306 __________ St L 6263 -3533 _____

#1 DST 3168-3325 (CG) 65", 1388' sli gcsw, IFP 155, FFP 665#,

FBHP 770#/30".

#2 DST 3402-3458 (CG) 1 hr, 765' gcsw, IFP 63#, FFP 358#,

FBHP 779#/30".

#3 DST 4950-81 (LKC) failed, tool stuck.

#4 DST 5144-95 (Miss) 0 60", GTS 2", ga 2,310 MCFG/45", R 10'

gcm, IFP 366, FFP 311, FSIP 1497#/30".

#5 DST 6194-6330 (St G-St L) 0 75", R 360' gcm (salty), ISIP

1952/60, IFP 105#, FFP 147#, FSIP 1504/30.
#6 DST 6049-6100 (Che-St. Gen) (str-pkr) op 60", R 20' M, ISIP
1630/38, IFP 20, FFP 30#, FSIP 110/30.
RTD 6330. 5½" @ 5906/350, MICT, ran G/R log.
24/5770-76. 40/5784-96. ga 1200 MCF (nat), A/500 M
g 2000 MCF. A/20000 (15%). swb ld, g 2750 MCF/12 hr BD.
2000 MCF. Chest 5770-96. SI.

LIBERAL ELECTRIC LOG TOPS

2732 TB

Winfield 2713 (+19)
Heebner 4299 (-1567)
Lanning 4440 (-1708)
Harnston 5118 (-2386)
Morrow 5646 (-2914) T 104'
No sand by operator
Chester (opr) 5750 (-3018) 12 hr BD g 2,000 MCF /
St. Gen 6032 (-3300)/tot 360' GCKN
St. Louis 6262 (-3530)/
TD 6330