

KANSAS DRILLERS LOG

API No. 15 —————
County Number

Operator

Henry B. Kelsey

Address

79 Wall Street, New York, New York 10005

Well No.

1

Lease Name

Randall

Footage Location

330

feet from (N) line

1320

feet from (E) line

Principal Contractor

Gabbert-Jones

Geologist

Tom Hammond

Spud Date

12 17 76

Total Depth

5400'

P.B.T.D.

Date Completed

1 21 77


Oil Purchaser

S. 6 T. 33S R. 21W X
W

Loc. NE/4

County Clark

640 Acres



Locate well correctly

Elev.: Gr.

2006

DF 2012'

KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	103/4"	8 5/8"		680'	Hal Lt. Portland	350 150	10 sacks calcium chloride
production	6 3/4"	4 1/2"	9.5	5396'	50/50 Pozmix	200	3% gel 18% salt 3/4% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	1/2" jet	5300-5308'
TUBING RECORD					
Size	Setting depth	Packer set at			
2 3/8"	5280'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1000 gals. 7.5% HCL	5300-5308'
20000 gals. 3% gel acid W/ 16000 lbs. 20/40 sand	same

INITIAL PRODUCTION

Date of first production 1 21 77		Producing method (flowing, pumping, gas lift, etc.) flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas 1,400 MCF	Water 7 bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold) Northern Natural Gas Co.			Producing interval (s) 5300-5308"		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

