



DRILLER'S LOG

P.C. Ind
11-33-21W

12/29/81

Paragon Petroleum Corporation
410 Seventeenth Street
Suite #1215
Denver, Colorado 80202

Bessie Bare #1
Cntr. of the SW of Sec.11-33S-21W
Clark Co., Kansas

Commenced: December 12, 1981
Completed: January 18, 1982

Surface Casing: Drilled 723' of 12½" hole.
Ran 18 jnts. of new 23# new 8 5/8" pipe, total
724 set at 723 KB. Cemented with 275 sks. of
lite, 2% CC, ¼# Flo-cile, followed with 150 sks.
class H, 3% CC. Finished cementing at 8 am.
Plug did not hold. 1 inched with 200 sks. of lite
3% CC. Lost circ. at 260' never got circ. back.
12/30/81 started drilling new hole.

Total Depth: 5500'

FORMATION	FROM	TO	REMARKS
Surface	0'	1657'	LTD: 5492'
Red Bed	1657'	2114'	TD: 5500'
Lime & Shale	2114'	5500'	

RECORDED
STATE OF KANSAS

JAN 25 1982


COUNTY CLERK
WILLIAM K. KATZ

I certify that this is a true and correct copy of the log on the above captioned well to
the best of my knowledge.

NRG Drilling, Inc.

By Elmer Jack Taylor
Elmer Jack Taylor, Vice-President

Subscribed and sworn to before me this 22 day of January 19 82



Marrnell Pribble
Marrnell Pribble

My commission expires: 8-20-83