

✓ 16-33-21W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ASHLAND OIL & REFINING CO.
Farm- Folks No. 1

SEC. 16 T. 33 R. 21W
SW NE SW

Total Depth. 5492'
Comm. 11-18-61 Comp. 12-8-61
Shot or Treated.
Contractor. Graham-Michaelis Drlg. Co.
Issued. 3-31-62

County Clark
KANSAS



CASING:

8 5/8" 580' cem w/450 sx.
4" 5484'

Elevation. 1970' RB

Production. 3,700,000 CFG

Figures Indicate Bottom of Formations.

red bed & sand	326
red bed & shells	362
Dry Drilling	600
sand & red bed	1166
red bed	1280
Anhydrite & shale	1592
red bed	1870
shale & lime	2085
lime	2290
lime & shale	2495
lime	2937
lime & shale	3357
shale & chalky lime	3485
chalk & lime	3915
chalk, lime & shale	4238
lime & shale	4373
shale	4517
lime & shale	4550
shale & shells	4650
lime & shale	4794
lime	5136
lime & shale	5206
lime	5492 RTD
Total Depth	

TOPS: SCOUT

Heebner	4295
Toronto	4348
Lansing	4517
Morrow	5358
Morrow Sand	5365