

23-33-21W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

SINCLAIR OIL & GAS CO.
Company- SHAMROCK & SOLAR
Farm- Combrine Gas No. 1-A
Combrink Unit

SEC. 23 T. 33 R. 21W
C NE SW

Total Depth. 5416'

Comm.

Comp.


County Clark

KANSAS

Shot or Treated.

Contractor.

Issued. 4-16-60



Elevation. 1845

Production. Dry

CASING:

20" 63" cem. w/250 sx.
13 3/8" 514' cem. w/550 sx.
8 5/8" 2470' cem. w/300 sx.

Figures indicate Bottom of Formations.

red bed	425
red bed & lime	650
red bed, shale & lime stks	990
shale & shells	1570
shale & lime stks.	1665
shale & shells	1983
shale & lime	2050
lime & shale	2240
lime	2984
lime & shale	3136
shale & lime	3535
lime	3829
lime & shale	3950
shale & lime	4146
sand	4190
shale & lime	4315
lime	4403
lime & shale	4611
lime	4807
lime & shale	4972
shale	5022
lime	5128
shale	5155
lime	5224
lime & shale	5332
sand	5352
shale & lime	5362
lime, shale, chert & sand	5392
chert & sand	5396
lime	5415RTD
lime	5416
Total Depth	

TOPS: SCOUT

Elgin Sand	4136
Heebner	4259
Brown Lime	4451
Lansing	4484
Cherokee	5145
Morrow	5280
Morrow Sand	5322
Mississippi	5396