

KANSAS DRILLERS LOG

API No. 15 — 025 — 20,310  
 County Number

S. 26 T. 33S R. 21 E W  
 Loc. 300' E of C NW SE  
 County Clark

Operator  
 Hummon Corporation

Address  
 400 One Main Place, Wichita, Kansas


Well No. #1 Lease Name Hazen

Footage Location  
 660 feet from (N) (S) line 660 feet from (E) (W) line

Principal Contractor D. R. Lauck Oil Company Geologist Steve Miller

Spud Date 7/16/79 Total Depth 5406 P.B.T.D. 5388

Date Completed 7/26/79 Oil Purchaser



Locate well correctly  
 Elev.: Gr. 1841  
 DF 1844 KB 1846

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8-5/8	23#	595	Common	400 sx	2% gel 3% cc
Production		4 1/2	10 1/2#	5426	Halco-Lite	25 sx	
					60-40 Poz	125 sx.	18% salt, 3/4 of 1% CFR2.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	SSB	5374-78

Size	Setting depth	Packer set at
2-3/8"	5352	---

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
---	

INITIAL PRODUCTION

Date of first production -- Producing method (flowing, pumping, gas lift, etc.)  
 flowing

RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB
		300,000		

Disposition of gas (vented, used on lease or sold) Producing interval (s) 5374-78

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator  
Hummon Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS,  
DRY HOLE, SWDW, ETC.:  
gas

Well No.  
#1

Lease Name  
Hazen

S 26 T 33S R 21 <sup>EX</sup> W

### WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,  
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 OP 45-60-90-120 Strong blow Gas to surface 40 min. 2nd opening gauged 34,000 to 205,000 CFG & stabilized FP 255, 196-363 SIP 1662-1662 Rec. 135' thin gas cut mud, 640' gas cut foamy water	5379	5406		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

*Wilber Berg*  
Signature

Wilber Berg

Title

10/8/79

Date