

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

28-33-21W


Company. THE ATLANTIC REFINING CO.
Farm. Dennis Gas Unit No. 1

SEC. 28 T. 33 R. 21W
C NE/4

Total Depth. 5530'
Comm. 12-11-59 : mp. 1-11-60
Shot or Treated.
Contractor. Fleet Drilling Company
Issued. 3-12-60

County Clark

KANSAS



Elevation. 1897 DF

Production. 2,000,000 CFG

CASING:

16" 80' cem. w/150 sx.
10 3/4" 538' cem.w/400 sx.
7" 2730' cem. w/200 sx.
4 1/2" 5539' cem. w/150

Figures Indicate Bottom of Formations.

surface hole	546
red bed & sand	650
shale, red bed & lime stks.	1135
red bed w/lime stks.	1526
shale & shells	1680
shale & anhydrite	2268
anhydrite	2368
anhydrite & shale	2416
shale, anhydrite & junk iron	2432
anhydrite & iron	2467
anhydrite & shale	2572
anhydrite, shale & junk	2584
shale & anhydrite	2748
shale, sand & anhydrite	2795
shale & lime	2832
shale, sand & lime	2899
shale & lime	2952
chalk, shale & lime stks.	3003
shale & lime	3105
shale, lime & chalk	3194
chalk, shale & lime stks.	3265
chalk, shale, sandy lime & lime	3385
lime & shale	3476
chalk, shale & lime	3636
shale & lime	3778
sand, lime & shale	3810
shale & lime	3910
lime & sandy shale	4012
shale & lime	4593
lime	4639
lime & sandy lime	4690
shale, lime & sand	4747
lime	4830
lime & shale	4918
lime & shale strks.	4981
shale & lime	5147
lime	5159

lime & shale	5272
lime	5292
lime, sandy lime & shale	5361
sandy lime & shale	5380
lime DST #1	5381
sandy lime & shale	5458
shale, sandy lime & lime	5475
sandy lime & shale	5508
sandy lime	5510
lime	5530
Total Depth	
TOPS: SCOUT	
Elgin	4154
Heebner	4270
Lansing	4464
Marmaton	5038
Cherokee	5189
Morrow	5309
Morrow Sand	5342
Mississippi	5447