

Russell KAN.
Shelbourne

Field Harper Ranch

State Kansas County Clarke
Company Jones & Farmer

Farm Ed Hoffman Well No. #1

Sec. 34 Twp Blk 335 Range Survey 21W

fr N fr E fr S fr W

of C 5 E N W

Contractor ~~Hart~~ (Ashland FO)

Remarks D & M Nalg.

Comm. 3-14-55 Comp. 6-8-55

Elev. 1920 T. D. 5480 P. B. 5436

Pay 5412-32 38° Gvty

T. R. 9,600 mcf 11 bopd
R. P.

Casing Record: 13 3/8 7
20 10 3/4 5 1/2 5478/200
16 8 5/8 2375/1380 Same

Surface around	Tops
2400'	Mon rd 5393
Ø 1560	MISS 5451
Ø 3252	

MAR 23 1955

MAR 30 1955

APR 6 1955

Ø 4844

DST 5390-99 op/hr.
gd blo down 30 m
rec 29' mud BN 190/20

DST 5399-5425 op/hr.
gts in 2 1/2 min MAX g - 1,250 mcf
rec 90' gcm FP 112-200
BN 180/20

DST. 5427-55 op/hr.
gts in 4 min MAX g - 240 mcf
rec 120' gcm BN SIP 190/20

D.S.T. 5452-80 op 1 m. new 15' mud FPO-0 PH 0/

RTD 5480^{2m} Schl

5 1/2' @ 5478/200

Woe

Schl Elgin 4221

APR 13 1955

Mon sh 5373

RUCT

" sd 5393

" " 5412

" " 5444

20 apr co to 5465 RA log p48/5445-59 gts m 9 min. MISS 5454

Apco swab & bailed 18 boph g-15,000 m
run thy & total frac 5000 10,000

Swab & planned 1 boph then open thy
pulled thy & set plug C5436

P120/5412-32 run thy & total
frac 5000 sd 10,000 swabed & flowing

load
27 apr planned load plus 15 boph
then 1/2" ch gas granger 5,000 m

FTP 900#

FCP 1000#

MAY 4 1955

MAY 11 1955

MAY 18 1955

Flow 1 1/2 boph 1/2" ch.
gas gained 4,500 m est 38°C ty

MAY 25 1955

JUN 1 1955

JUN 8 1955

1 3/4" ch g-9,600 m

plus 1 1/2 boph TP 700#