

6-210W Map No. K-83OPER ANADARKO PRODUCTION COMPANYLiberal, Kansas#1 DODD-MADDEN "A"CONTR Moran BrothersFIELD Evalyn-Condit (Lans-Marm-Miss)I.P. F 287 BOPD, Chest Pf 6105-12S-T-R 21-33S-33WSPOT C NW SECO SEWARD, Ks.ELEV 2847 KB

(GR Logs:)

WLT #1 (Mar) 5077½-80, Op 1 hr, R .12 cu ft gas / 3800' cc wtr (33% form W) SP 50#

WLT #1-A (Mar) 5077½-80, Op ½ hr, R .1 cu ft gas / 450' cc wtr (40% form W), FSIP 1650#/30"

WLT #2 (Mrw) 5755½-58, Op 90", R .35 cu ft gas, ISIP less than expl. press, SP 50#, No FSIP,

DST #1 (Chest) 6080-6220, Op 45", GTS/7", TSTM, Ga 38, 000 CFGPD/15", Stab, R 305' HO&GCM, ISIP 2190#/45", FP's 95#-122#, FSIP 2148#/45"RTD 6220, Ran Log, 4½" @ 6220' w/210 Sx.

Pf 14/6105-12 (Chest), NTN, 500 (15%) Acid, § 1d, § & flo 192 BO/20 hrs, Frac 7500 Gell A x 7500# sd, § & flo 1d, § & Flo 77 BO/9 hrs, Ran 2 3/8" tbg to 6117, Flo 12 BOPH/6 hrs thru tbg (Gr 40.5 deg), Flow 287 BO/24 hrs, NW, Gr 40.5 deg, SICP 632#/218½ hrs, BHP 2133# at 6110', Chest 6105-12 - COMPLETED on 6-18-65

Winf 2698 / 137

CG 2946 - 111

Tor 4276 -1441

Lans 4392 -1557

Mor 5072 -2237

Mrw 5634 -2799

L/Mrw sd 5770 -2935

B/Mrw sd 5826 -2991

Chest 5842 -3007

Chest sd 6064 -3229

B/sd 6184 -3349

Ste G 6184 -3349

LTD 6220 -3385

Data Inc

MISC DATA

GEOL _____

FTG _____

SUPPT _____

CSG 8" @1605' w/850 Sx.ELEV 2834 GRK-5 2844 DFSPUD DATE 5-16-65

DRLG COMP _____

FR by DATA 5-14-65COMP by " 6-24-65

LIBERAL ELECTRIC LOG TOPS

2835 GL

Winfield 2694 (-141)

Heebner 4256 (-1421)

Toronto 4276 (-1441)

Lansing 4392 (-1557)

Marmaton 5070 (-2235)

Morrow 5634 (-2799)

"S-3" 5776 (-2941) 12/26

Chester 5828 (-2993)

Sand 6100 (-3265) 8/22; HO&GCM; ϕ Flo 287 BOPD

Ste. Gen 6200 (-3365)

TD 6220