


150' S of C NW NE

1-73W Map No. K-84  
OPER ANADARKO PROD. CO. - Liberal, Ks.



S-T-R 21-33S-33W  
SPOT App S/2 NW NE  
CO SEWARD (Ks)  
ELEV 2836 GR

#1 SWAN "A"  
R Moran Brothers

(GR Log)

FIELD Evalyn-Condit Field (Lan, Mrw, Miss)  
I.P. Ga 40,160,000 Cfgpd, Flo 4 B Cond/5 hrs,  
Gr 59.4°, Mrw 5660-75

Herr	2579	+	257
U/Kri	2606	+	230
L/Kri	2640	+	196
Winf	2694	+	142
U/FR	2750	+	86
L/FR	2810	+	26
Wre	2912	-	76
C Gr	2952	-	116
Hb	4236	-	1400
Tor	4274	-	1438
Lan	4386	-	1550
Mar	5058	-	2222
Mrw	5620	-	2784
U/Mrw sd	5658	-	2822
B/sd	5678	-	2842

DST #1 (Mrw) 5608-5740, Op 10", Ga 7,020,000 Cfgpd/5",  
Ga 9,980,000 Cfgpd/10", R 3' sli dist CM, ISIP 1589#/  
40", FP's 1500-1506#, FSIP 1589#/40", RTD 6242,  
Logs, 4½" @5900 w/225 sx.

RUCT - GRN Log, Pf 10/5670-75, 20/5660-70 (Mrw),  
Ga 20,432,000 Cfgpd/8½ hrs & 7½ BF - 2 3/8" tbg @5651,  
Ga 7,112,000 Cfgpd/2 hrs thru tbg, Ga 14,252,000 Cfgpd/  
2 hrs thru annulus,

5 Pt Cal OF; Ga 40,160,000 CFGPD, FTP 825#, FCP  
1328#, Flow 4 B Cond in 5 hrs, Gr 59.4 deg, Mrw 5660-  
75 - COMPLETED on 12-30-65

Data, Inc

Mrw sd	5808	-	2972
B/sd	5836	-	3000
Chest	5840	-	3004
Ste G	6197	-	3361
LTD	6242	-	3406
RTD	6242	-	3406

Correction (11-16-65) Was C NW NE - Is App S/2 NW NE  
Corrected by operator

L-S 2846 EOP  
2836 GL

MISCEL DATA

GEOL	_____	ELEV	<u>2845 DF</u>	SPUD DATE	<u>11-23-65</u>
FTG	<u>810' NL x 1980' EL</u>		<u>2848 KB</u>	DRLG COMP	_____
SUPPT	_____			FR by DATA	<u>11-8-65</u>
CSG	<u>8" @1614 w/1000 sx. 4½" @5900 w/225 sx.</u>			COMP by "	<u>1-6-66</u>

*Revised*

LIBERAL ELECTRIC LOG TOPS

2836 GL

Winfield 2694 (+442)

Heebner 4254 (-1418)

Toronto 4274 (-1438)

Lansing 4386 (-1550)

Marmaton 5058 (-2222)

Morrow 5620 (-2784)

"S-2" Sand 5658 (-2822) 16/20;  $\phi$  g 40,160 MCF, flo 4 BCond/5'

"S-3" Sand 5808 (-2996) 2/8

"S-3" Sand 5822 (-2986) 6/14

Chester 5838 (-3002)

Ste. Gen 6196 (-3360)

TD 6242