

12-33-22W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- ATLANTIC REFG. CO.  
Farm- Rosebush No. 1

SEC. 12 T. 33 R. 22W  
C SE

Total Depth. 5400'  
Comm. 4-12-62 Comp. 5-5 -62  
Shot or Treated.  
Contractor.  
Issued. 11-24-62

County Clark KANSAS



Elevation. 1898' DF

Production. 5,000,000 CFGPD

CASING:

8 5/8" 626' cem w/570 sx.  
2 1/2" 5399' cem w/225 sx.

Figures Indicate Bottom of Formations.

COMPLETE DRILLERS LOG NOT AVAILABLE:

TOPS: SCHLUMBERGER

Lansing	4392
Marmaton	4952
Cherokee	5078
Morrow	5220
Sand	5242
Chester	5276
St. Genevieve	5326

DST #1 5237-5310', op 60 min, gas - 3 min.,  
5 min-1,400 MCF, 10 min.-1,350 MCF, 15  
min-2,000 MCF, 30 min-2,005 MCF, 45 min  
2,250 MCF, 60 min-2,250 MCF, rec. 5' GCM,  
ISIP 1980/30 min, FSIP 1935/30 min., FP  
345-345.

Perf. 5243-47', 500 Acid, swb. & flow,  
Frac 13.8 x 19, swb. & flow, 2,000 MCF  
on 1/4" ch., 5,000 MCFGPD.