

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

24-33-22W


Company. JOHN P. BOOTH
Farm. Ella McMinimy No. 1

SEC. 24 T. 33 R. 22W
C SW

Total Depth. 5440'
Comm. 3-23-61 Comp. 4-17-61
Shot or Treated.
Contractor. Patton Drilling Co.
Issued. 3-17-62

County Clark

KANSAS



Elevation. 1830' RB

Production. 7,000,000 CFG

CASING:

13 3/8" 38' W/4 Yds ready mix
9 5/8" 460' cem w/150 sx.
7" 2454' cem w/600 sx.
4 1/2" 5439' cem w/100 sx. Figures Indicate Bottom of Formations.

clay & sand	120
red bed & sand	275
Dry Drilled	460
red bed & shells	1100
shale, shells & salt	1540
shale & shells	1775
Anhydrite & shale	2130
lime & shale	2265
lime	2455
lime & shale	2613
lime	2680
lime & shale	2965
chalky lime & shale	3115
lime & shale	3245
chalky lime & shale	3353
lime & shale	3575
chalky lime & shale	3663
lime & shale	4000
sandy shale	4175
shale w/lime streaks	4210
lime & shale	4325
lime	4755
lime & shale	4790
lime	4987
lime & shale	5036
lime	5120
lime & shale	5185
lime	5230
lime & shale	5330
sandy lime & shale	5337
lime & shale	5433
lime w/chert	5440
Total Depth	

TOPS: SCOUT
Council Grove
Elgin
Heebner
Toronto
Lansing
Cherokee
Morrow
Mississippi
St. Genevieve

2734
3996
4198
4236
4415
5120
5270
5336
5360

