

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

25-33-22W


Company- E. H. ADAIR OIL CO.
Farm- York No. 1

SEC. 25 T. 33 R. 22
C NW

Total Depth. 5406'
Comm. 10-1-60 Comp. 10-16-60
Shot or Treated.
Contractor. Graham-Michaelis Drig.
Issued. 5-27-61

County Clark

KANSAS



CASING:
13 3/8" 383' cem w/450 sx.
4 1/2" 5398' cem w/200 sx.

Elevation. 1956' KB

Production. 5,000,000 CFG

Figures indicate Bottom of Formations.

shale & lime	4000
shale	4088
lime	4093
sand	4142
shale	4168
sand	4180
lime	4194
shale	4268
lime	4284
black shale	4288
lime	4299
black shale	4303
shale & lime	4324
lime	4340
shale	4378
lime	4410
shale	4499
lime	4507
shaley lime	4533
lime	4639
cherty lime	4649
lime	4734
shale	4742
lime	4792
shale	4797
lime	4939
shale	4945
lime	5001
black shale	5003
lime	5205
black shale	5208
lime	5227
black shale	5230
lime	5263
shale	5271
lime & shaley lime	5393
sandy lime, show of gas	5393
sand, show gas	5406
Total Depth	5406 RTD

TOPS:
Elgin Sand 4093
Heebner Shale 4284
Lansing 4499
Cherokee Formation 5205
Morrow Zone 5374
Morrow Sand 5398

DST #1 5386-5406', gas to surf. in 1 min.
Gauged 3,100,000/2 min, 4,326,000/5 min;
5,100,000/10 min, ISIP 1890#/20 min,
FSIP 1910#/20 min, IFP 1330#, FFP 1350#.

