

Geological Survey

IMPORTANT
Kans. Geo. Survey request
samples on this well.

15-025-20244

WICHITA BRANCH
KANSAS DRILLERS LOG

S. 34 T. 33 R. 22 ^{NE}_W

API No. 15 — 025 — 20,244
County Number

Loc. C NEM


Operator
Weaver Exploration Co. % Oil Prop. Mgmt.

County Clark

Address
300 Insurance Bldg. Wichita, Kansas 67202

640 Acres
N

Well No. # 1 Lease Name
Broadie



Footage Location
660 feet from (N) ~~MX~~ line 660 feet from (E) (~~W~~) line

Elev.: Gr. 1890

Principal Contractor
Gabbert-Jones, Inc. Rig #3 Geologist
Kenneth Johnson

Spud Date
December 26, 1978 Total Depth
5541 P.B.T.D.

Date Completed
January 9, 1979 Oil Purchaser
None

DF 1892 KB 1895

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface Casing	12½"	8-5/8"	24#	542'	Common--Top Common--Bottom	200 200	Both cases 2% gel 3% CaCl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 8838 So. Mainline, D.O. Box 12888, Wichita, Kansas 67217. If you wish to contact the Geological Survey of Kansas, Lawrence, Kansas 66044, call 82-2-125. Drillers Logs will be on open file in the Oil and Gas L.

Weaver Exploration Co. DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Dry Hole

Well No. 1 Lease Name BROADIE

S 34 T 33S R 22W ^E/_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Copy of Driller's Well Log attached			Heebner	4228
DST #1 5371-5541' Misrun			Brown Lime	4415
			Lansing-K.C.	4430
			Cherokee	5148
DST #2 5388-5541' 45-45-45-45			Morrow Shale	5300
Strong blow, decreasing to fair blow			Chester Lst.	5381
Very weak blow on 2nd open			Chester Sst.	5400
Rec: 900' rotary mud			St. Genevieve	5424
IFP 542-532#			Total depth	5541
ISIP 1384#				
FFP 532-532#				
FSIP 1178#				
DST #3 5362-5454 (Straddle Test) 45-60-45-60				
Strong blow decreasing to weak each open period				
Rec: 240' rotary mud				
IFP 106-106#				
ISIP 341#				
FFP 149-127#				
FSIP 320#				

Electra--Radiation Accurlog,
Density & 2 Arm Caliper

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<div style="text-align: right; margin-bottom: 5px;"> Signature </div> <div style="text-align: right; margin-bottom: 5px;"> W. H. Peachee President--Oil Property Management, Inc. Title </div> <div style="text-align: right;"> February 22, 1979 Date </div>
---------------	--

34-33-22W

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Broadie #1
 NE-NE Sec 34-33S-22W
 Clark County Kansas

Commenced: 12-26-78

Completed: 1-9-79

Operator: Oil Property Management, Inc.

Depth		Formation	Remarks
From	to		
0	1550	Redbed	Ran 14 jts of 8 5/8" csg set @ 542' Cemented Bottom w/200 sks Common 2% Gel 3% CC - Top w/200 sks Common PD @ 6:00 a.m. 12-27-78
1550	2171	Redbed-Shale	
2171	2325	Lime-Shale	
2325	2700	Shale-Lime	
2700	3040	Lime-Shale	
3040	3244	Shale-Lime	
3244	3445	Lime	
3445	3640	Lime-Shale	
3640	3809	Shale-Lime	
3809	3965	Lime	
3965	4175	Lime-Shale	
4175	4316	Shale-Lime	
4316	4465	Lime	
4465	4650	Lime-Shale	
4650	4784	Shale-Lime	
4784	4872	Lime	
4872	4976	Lime-Shale	
4976	5050	Shale-Lime	
5050	5140	Lime	
5140	5360	Lime-Shale	
5360	5416	Lime	
5416	5480	Lime-Shale	
	5480 - TD		DRY & ABANDONED

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton
 JAMES S. SUTTON TT