

SA 8-166


Best Scanned Copy

1935 517
ELEV. 1935 KB

MAP NO. _____
 STATE MO. COUNTY Clark SEC. 31
 OPERATOR E. H. Adair Oil Co. - Winona, Kansas LOC. U NW SE
 WELL NO. 1 FARM NAME York "C" FT. FROM _____ LINE _____
 POOL Wildcat (TD 5690) FT. FROM _____ LINE _____
 FR. 8-5-61 SPUD 7-31-61 COMP. 8-17-61

CONT./GEOL. Graham-Michaelis Tools

	COMPLETION RECORD			
	NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a	_____	_____	_____	_____
b	_____	_____	_____	_____
c	_____	_____	_____	_____
d	_____	_____	_____	_____



D & A _____ D & A (X) _____

SIP#	FI TP #	FI CP#	SIBHP
_____	_____	_____	_____

GOR.	GR.	PBDT	TD
_____	_____	_____	<u>5442</u>

CASING - CEMENT RECORD	
SIZE	DEPTH
<u>8 5/8"</u>	<u>628</u>
	<u>350</u>

OPERATOR E. H. Adair Oil Co. WELL NO. #1 York "C" ELEV. 1935 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Heebner	4257		Elgin	4060	
Lansing	4455		Heebner	4216	
Morrow	5293		Lansing	4431	
Ste Genevieve	5377		Cherokee	5135	
			Morrow	5289	
			Morrow Sand	5360	
			Mississippian	5366	

Spud 7-31-61, 8 5/8" @ 628 w/350 sz.
 DST #1 (Morrow & Mississippian) 5357-76, op 1 hr, sh blow 1 hr
 Rc 25 mod, PSIP 240/30 mins, FP 85-135, PSIP 175/30 mins.
 DST #2 (Mississippian) 5380-5425, op 90 mins, fr blo 90 mins,
 Rc 8" mod, PSIP 205/20 mins, FP 80-60, PSIP 580/30 mins
 TL 5442, logs.

B & A 8-17-61
 COMPLETE.

5289
 1935
 -3354

5360
 1935
 -3425