

Meade Co.

22-33-30

J. Donoghue #1 Powell

CSENE

2715 KB

Winfield 2798 (-83)

TD (^{Schl.} ~~Dritter~~) 5888 (-3073)

Heebner 4424 (-1709)

TD (^{Dritter} ~~3073~~) 5805 (-3106)

Douglas 4435 (-1720)

Lansing 4566 (-1851)

Marmaton 5202 (-2487) - 45680 PD

Morrow 5702 (-2987)

S₂ 5710 (-2995) T B por 4

S₂ 5723 (-3008) T 7, por 6

Chester 5760 (-3045) 5 M offer frac

Bob Lang Serv

5

Field Novinger

State Kansas

County Meade

Company James Donoghue

Farm Powell

Well No. 1

Sec. 22 Twp. Blk. 33S

Range Survey 30W

fr N

fr E

fr S

fr W

of C SE NE

Contractor Rocket

Remarks

Comm. 1-24-56

Comp. 5/29/56

Elev. 2712 DF

T. D. 5805

P. B. 5330

Pay 5266-75

I. P. 56 BOPD

R. P.

Casing Record: 13 3/8

7

20 10 3/4

5 1/2 5787/250

16 8 5/8

Log-TOPS

	RURT	Tops
FEB 1	Ø 3131	K.C. 4568
FEB 8	Ø lost circ 3205 -	Marm 5205 (NOVINGER) PAY zone 5266-75
FEB 15	TTD 3035 DST 3626-36-0P	CCR 5505
FEB 15	1 1/2 hrs fr blo we 1270' SW Atoka	5596
	FP 25-573- BH 920/20	Marm 5702
	DST 5250-5290 op 1M 12" Chest	5770
	RTS 5" MCF 240 MCF @	Pay zone 5787-5805
	end 155 MCF Dec 930' oil.	
	FP 0-285- BH 835/30	
FEB 22	Ø 15680-5730 Me 50'	
	11' lmy shale	
	11' shale - sd streaks	
	2' shly sd. bleed + g.	
	7 1/2' shale.	
	5 1/2' sd. - bleed + g -	
	8' shly sd.	
	1/2' bl sh.	
	4 1/2' lmy sd. foss. minor bleed + g.	
	Ø 5732-5980- Dec 48	

RTD 5780 - run log - prof to run pipe

old Dope

FEB 29 Plot 2 - 5732-5780 - run 32'

- 11' lost
- 3' shale
- 2' low sdy. oil stain
- 3' sdy. fm gr. shaly - odor -
- 7' bl shale -
- 11' long shale - ~~oil~~
- 9' low - bleed out gas.
- 2' thin low.

RTD 5780

~~New Dope -~~
set 5 1/2 5787/250
WOT

MAR 7 ✓ MAR 14 ✓ MICT to CO.

MAR 21 DD to 5805 g 1,500 MCF - A/500 7.5%
prod 4000 P/1000 7.5 g 5,000 MCF SIP 1516th

MAR 28 ✓
APR 4 ✓ WOT.

chest

APR 11 New pipe pl @ 5320 P/30/
5266-75 - A/500 m amber bleed flo
60 BO in 12 hrs run 1 to 5325 5'
SIP 280th WOT + Tanks.

APR 18 ✓ MAY 2 ✓

APR 25 ✓ MAY 9 ✓ flowed 40 BOPD by heads
P.O.P. MAY 16 ✓

MAY 23 flowed 30 → 40 BOPD by
heads - P.O.P.

pumped 40-50 BOPD. for 2 days
WOT

MAY 30 ✓ STATE TEST
pumped 56 BOPD.

[Handwritten signature]