

X

A-4-84 K-84
 MAP NO. _____ ELEV. 2746 DF
 STATE Kansas COUNTY Seward SEC. 23 Twp 33S Rge 31W
 OPERATOR Republic Natural Gas Co.-Hugoton, Ks. LOC. C SW SE
 WELL NO. 1 FARM NAME Wheatley "A" FT. FROM _____ LINE _____
 TOL. Kismet (PD 6000) FT. FROM _____ LINE _____
 FR. 1-31-61 SPUD. 2-8-61 COMP. 3-30-61
 CONT./GEOL. Moran Bros.

COMPLETION RECORD
 NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD
St. Louis 5885-93 32 500 MA
 b _____
 c _____
 d _____

d I. P. OIL/DIST. F/297 BOPD GAS _____ M.C.F.P.D. _____ CHK. 3/8" HRS. 24
 b " " " " " "
 c " " " " " "
 d _____

D & A ()
 SIP# 265 FI TP # 120 FI CP# _____ SIBHP _____
 GOR. _____ GR. 39° PBTD 5953 TD 5989

CASING - CEMENT RECORD
 SIZE DEPTH W/SAX. SIZE DEPTH W/SAX.
8 5/8" 2420 1604 _____
5 1/2" 5987 935 _____

OPERATOR Republic Nat'l Gas WELL NO. #1 Wheatley "A" ELEV. 2746 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			Herrington	2618	
			Winfield	2652	
			Upper Ft. Riley	2713	
			Lower Ft. Riley	2770	
			Council Grove	2980	
			Heebner	4250	
			Toronto	4290	
			Lansing	4410	
			Lansing "A"	4479	
			Lansing "D"	4860	
			Marmaton	5038	
			Cherokee	5186	
			Morrow	5510	
			Morrow Sand	5527-32	
			Morrow Sand	5549-55	
			Chester	5580	
			Ste Genevieve	5610	
			St. Louis	5705.	

Spud 2-8-61, 8 5/8" @ 2420 w/1604 sx.
 DST #1 (Krider) 2622-50, op 60 mins, fr blo, Rc 10' GCM/NS,

A-4-84

SHEET NO. 2 MAP NO. _____
STATE Kansas COUNTY Seward SEC. 23 Twp 33S Rge 31W
OPERATOR Republic Nat'l Gas Co. LOC. C SW SE
WELL NO. 1 FARM NAME Wheatley "A"

ISIP 148/30 mins, FP 0-0, FSIP 42/30 mins.

DST #2 (Council Grove) 2982-3108, failed.

DST #3 (Council Grove) 2968-3108, op 1 hr, fr-gd blo, Rc 180' mud + 180' SGCM + 90' SSGCM, ISIP 696/30 mins, FP 147-274, FSIP 654/30 mins.

DST #4 (Council Grove) 3097-3210, op 1 hr, GTS 3 mins, Ga 239 MCF/5 mins, Inc to 648 MCF/60 mins, Rc 470' GCM + 180' SGCM, ISIP 610/30 mins, FP 0-150, FSIP 610/30 mins.

DST #5 (Toronto) 4297-4330, op 1 hr, GTS 3 mins, Ga 2922 MCF/8 mins, Ga 3379 MCF/15 mins (Stab), Rc 10' GCM, ISIP 1295/30 mins, FP 600-578, FSIP 1272/30 mins.

DST #6 (Lansing) 4877-95, op 130 mins, Rc 565' oil + 10' HO&GCM, FP 89-156, SIP fld.

DST #7 (Marmaton) 5130-80, op 1 hr, GTS 2 mins, TSTM Rc 30' SGCM + 180' HO&GCM, ISIP 1657/30 mins, FP 22-67, FSIP 1657/30 mins.

DST #8 (Morrow) 5495-5577, op 1 hr, GTS 2 mins, Ga 4052 MCF/5

OPERATOR Republic Nat'l Gas Co. WELL NO. #1 Wheatley "A"

mins, Ga 4854 MCF/45 mins (Stab), Rc 1 GD, Gty 61.5°, ISIP 1862/30 mins, FP 735-735, FSIP 1862/30 mins.

DST #9 (Ste Genevieve) 5619-45, op 1 hr, GTS 12 mins, TSTM, Rec 40' GCM, ISIP 1717/30 mins, FP 42-42, FSIP 1620/30 mins.

DST #10 (St. Louis) 5755-95, op 1 hr, GTS 6 mins, Ga 265 MCF/5 mins. Dec to 246 MCF/35 mins, Stab, Rec 60' GCM, ISIP 1738/30 mins, FP 42-63, FSIP 1717/30 mins.

DST #11 (St. Louis) 5835-5900, op 110 mins, GTS 3 mins, Ga 331 MCF/10 mins. Dec to TSTM, OTS/45 mins, Flod 16.64 BO/30 mins, (Gty 36°), ISIP 1753/32 mins, FP 493-1273, FSIP 1707/30 mins.

DST #12 (St. Louis) 5900-71, op 1 hr, Rc 890' SGCM, ISIP 1632/30 mins, FP 63-105, FSIP 1546/30 mins.

RTD 5981, logs (Sj) to 5989, 5½" @ 5987 w/935 sx. MICT. CO. P/4/4990, SQ w/418 sx. CO. to 5953.

P/32/5885-93, tbg & pkr @ 5884, Swb/NS, 500 MA, Rc 1d, Flod 58 BO/2 hrs, 35/64" ck, FTP 80, SIP 265/40 mins. Flod 225 BO/13 hrs, 23/64" ck, Gty 38.4°, FTP 180.

P/4/4896-98, Set pkr @ 5778 w/BP @ 4930, ran tbg w/pkr to 4871. Swb 3/4 BFPH/5 hrs, 500 Ac, Flod 40 BO + wtr (no est/4 hrs. Flod 60 BO + 30 BSW/12 hrs, 3/8" ck, Gty 35°, FTP 150. SQ 4896-98 w/50 sx. CO to 5953, ran tbg w/pkr to 5740.

Lost swb in hole, rec fish. flod 168 BO/16 hrs, 3/8" ck, FTP
100#.

IP flod 297 BOPD, 3/8" ck, FTP 120#, Gty 39°, SIP 265/40 mins,
from St. Louis 5885-93.

LIBERAL TOPS

2748 KB

Winfield 2714 (+34)

Council Grove 2944 (-196) tst 648 MCF

Heebner 4274 (-1526)

Toronto 4296 (-1548) tst 3,379 MCF

Lansing 4410 (-1662) tst 565' oil (Lans/KC)

Marmaton 5038 (-2290) tst 180' HO&GCM

Morrow 5510 (-2762) T 70', Tss 11'

"S-2" 5527 (-2779) 2/5/ tst 4,854 MCF

"S-2" 5549 (-2801) 2/6/

Chester 5580 (-2832)

St. Gen 5620 (-2872)

St. Louis 5738 (-2990) flo 225 BO/13 hrs ; ϕ 297 BOPD

TD 5981

A-8-110

OWWO

MAP NO. _____

ELEV. 2746 ODF

STATE Kansas COUNTY Seward SEC. 23Twp 33S Rge 31WOPERATOR Republic Natural GasLOC. SW SEWELL NO. 1 FARM NAME Wheatley "A"

FT. FROM _____ LINE


POOL Kismet

FT. FROM _____ LINE

FR. _____ SPUD _____ COMP. 8-4-61

CONT./GEOL. _____

NAME PRODUCING INTERVAL	COMPLETION RECORD		PERF. W/HOLES	TREATMENT RECORD
	FROM —	TO		
<u>Morrow</u>	<u>5528-55</u>		<u>48</u>	<u>1000</u>
b _____				
c _____				
d _____				



I. P. OIL/DIST.	Tr	WTR	GAS	1626	M.C.F.D.	CHK.	HRS.	4
b "	"	"	"	"	"	"	"	"
c "	"	"	"	"	"	"	"	"
d	(Dually completed w/St Louis 5885-93)							

SIP# 1620 FI TP # _____ FI CP# _____ SIBHP _____GOR. _____ GR. 690 PBTD _____ TD 5989

SIZE	DEPTH	CASING - CEMENT RECORD	SIZE	DEPTH	W/SAX.
<u>5-1/2"</u>	<u>5987</u>	<u>935</u>			

OPERATOR Republic Natural Gas WELL NO. #1 Wheatley "A" ELEV. 2746 ODF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			Toronto	4290	
			Lansing	4410	
			Lansing A Zone	4479	
			Lansing D Zone	4860	
			Marmaton	5038	
			Cherokee	5186	
			Morrow	5510	
			Morrow Sand	5527-32	
			Morrow Sand	5549-55	
			Chester	5580	
			Ste Genevieve	5610	
			St Louis	5705	

Old Info: OTD 5989. 5-1/2" @ 5987 w/935 sx.

Was Completed from St Louis (5885-93) for 297 BOPD.

New Info: To Dual Complete. Re-entered.

P/16/5528-32, 12/5537-40, 20/5550-55. Set BP @ 5650, tbg w/pkr @ 5507, 10 hr BD, Ga 2, 410 MCF/D / 7 B Dist / 2 BL, 20/64" ck, FTP 850#, 1000-15% Ac, set 1 1/2" tbg thru pkr @ 5650 &

1½" tbg @ 5504. Morrow SITP 1620#. St. Louis SITP 0#,
SICP 0#.

IP 4 hr BD 1,626 MCF w/tr dist, Gty 69°, SIP 1620, from
Morrow 5528-55.

DUAL COMPLETION w/St. Louis Complete 8/4/61