


5-359 W
 MAP NO. FR & COMP SEC. 23 TWP. 33S RGE. 31W
 STATE Kans COUNTY Seward LOC. C SE SW
 OPERATOR Panhandle Dev. Co., Inc. 1980 FT. FROM N LINE
 WELL NO. 1 FARM NAME Wheatley (OWWO) 1980 FT. FROM W LINE
 Kismet ELEV. 2760 GR. 2762 E K.B.
 FR. 5/18/62 SPUD. COMP. 5/29/62 of SW/4

CONT. _____ /GEOL. _____
 NAME PRODUCING INTERVAL COMPLETION RECORD FROM - TO PERF. W/HOLES TREATMENT RECORD
 a _____
 b _____
 c _____
 d _____
 I. P. OIL/DIST. WTR. GAS M.C.F.P.D. CHK. HRS.
 b " " " " " "
 c " " " " " "
 d Water Input well in Glorietta 1037-97



D & A ()
 SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____
 GOR. _____ GR. _____ PBDT 1346 TD 6000
 CASING - CEMENT RECORD
 SIZE 8 5/8" DEPTH 1387 W/SAX. 300 5 1/2" SIZE DEPTH 1029 W/SAX. 50

OPERATOR Panhandle Dev. Co. WELL NO. 1 Wheatley (OWWO) ELEV. 2762 EKB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
KB Tops & Datums					
			Cong	2997	- 235
OTD (Miss) 6000	-3238		Hb	4267	-1505
			Tor	4305	-1543
OLD INFO: (Same Operator)			Lans	4424	-1662
5 1/2" @ 5997 w/400 sx.			Marm	5052	-2290
Comp as Miss well 6/9/61.			Chero	5210	-2448
			Morr	5535	-2773
NEW INFO: (May, 1962) MIR			Morr sd	5558-64	-2796
Shot off 5 1/2" csg @ 1850, Pulled Miss @ 1850				5608	-2846
up to 1250' cem w/50 sx.					
PBDT 1346. Perf 120/1037-97 (Glorietta) 2000 MA, Frac w/45000 Jell 2% Acid, no help (Split csg @ 957-1000 Acid out above Glorietta perfs) Set 5 1/2" csg @ 1029 w/50 sx. CO 1346 PBDT, Input 250 BSW/NT. (Rate 12 1/2 BWPM Comp 5/15/62. Glorietta perfs 1037-97.					

COMPLETED