

A-4-221

MAP NO.

K-84

STATE Kansas

COUNTY

SewardSEC. 23ELEV. 2752 KBTwp 33SRge 31WOPERATOR Republic Natural Gas Co.LOC. C NW SEWELL NO. 2 FARM NAME Wheatley "A"

FT. FROM _____ LINE


POOL Kismet (PD 6000)

FT. FROM _____ LINE

FR. 3-6-61 SPUD 3-5-61 COMP. 4-24-61CONT./GEOL. Moran Bros. Tools.

COMPLETION RECORD

NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a <u>St. Louis</u>	<u>5893-5908</u>	<u>32</u>	<u>3000 Ac</u>
b _____	_____	_____	_____
c _____	_____	_____	_____
d _____	_____	_____	_____



a I. P. OIL/DIST.	F/78 BOED	6/10 BWD	M.C.F.P.D.	CHK.	20/64	HRS.	24
b "	"	"	"	"	"	"	"
c "	"	"	"	"	"	"	"
d _____	_____	_____	_____	_____	_____	_____	_____

SIP# _____ FI TP # 80 FI CP# _____ SIBHP _____GOR. _____ GR. 36° PBTD 5949 TD 6009

D & A ()

SIZE	DEPTH	CASING - CEMENT RECORD	SIZE	DEPTH	W/SAX.
10 3/4"	2407	1845			
7"	5989	455			

OPERATOR Republic Nat'l Gas WELL NO. #2 Wheatley "A" ELEV. 2752 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			Herrington	2622	
			Winfield	2651	
			Upper Ft. Riley	2716	
			Lower Ft. Riley	2780	
			Council Grove	2988	
			Heebner	4259	
			Toronto	4296	
			Lansing	4418	
			Lansing "A"	4486	
			Lansing "D"	4876	
			Marmaton	5042	
			Cherokee	5192	
			Morrow	5519	
			Chester	5592	
			Ste. Genevieve	5622	
			St. Louis	5720	

4418
2752
-1664

See OWNED Ticket

Spud 3-5-61, 10 3/4" @ 2407 w/1845 sx.

Fished out DP @ 4664.

RTD 6009, logs to 6004, 7" @ 5989 w/455 sx. MICT. CO to 5949.

P 16/5904-08, 500 Ac. rec ld, flod 45 BNO/10 hrs, Gty 36°, flod 75 BO/17 hrs, 38/64" ck, FTP 20-50, SIP 360. flod 23 BO/24 hrs, 22/64" ck, FTP 20-40.

P 16/5893-97, set T w/pkr @ 5849, swb 40 BO/5 hrs. trt 5893-5908 w/500 MA, flod 30 BO/8 hrs, 3/8" ck FP 0-40, 2000 Ac, rec ld, flod 103 BO + 3.8% wtr/19 hrs, 3/8" ck, FP 75, Gty 36°, flod 78 BOPD, 20/64" ck, FP 80.

IP flod 78 BO + 6/10 BW/24 hrs, 20/64" ck, FTP 80, Gty 36°, from St. Louis 5893-5908.

LIBERAL TOPS

2752 KB

Winfield 2714 (+38)

C. G. 2954 (-202)

Heebner 4276 (-1524)

Lansing 4418 (-1666)

Marmaton 5048 (-2296)

Morrow 5520 (-2768) T 70', no Sand

Chester 5590 (-2838)

St. Gen 5630 (-2878)

St. Louis 5756 (-3004) ϕ 78 BO + 6-10 BW/24 hrs

TD 6000