

A-8-167

2752 KB

MAP NO. _____

OWWO

ELEV. 2731 GL

STATE Kansas COUNTY Seward SEC. 23Twp 33 S Rge 31 WOPERATOR Republic Natural Gas CompanyLOC. NW SEWELL NO. 2 FARM NAME Wheatley "A"

FT. FROM _____ LINE


POOL Kismet

FT. FROM _____ LINE

FR. _____ SPUD 5-30-61 COMP. 8-14-61

CONT./GEOL. _____

NAME PRODUCING INTERVAL	COMPLETION RECORD		TREATMENT RECORD
	FROM - TO	PERF. W/HOLES	
a <u>Toronto</u>	<u>4300-05</u>	<u>20</u>	<u>5000 Ac</u>
b <u>Lansing</u>	<u>4890-96</u>	<u>24</u>	<u>500 Ac</u>
c <u>St Louis</u>	<u>5822-88</u>	<u>30</u>	<u>2500 Ac</u>



d I. P. OIL/DIST.	WTR.	GAS	2,273	M.C.F.P.D.	CHK.	HRS.	75"
b " F/241 BO	" 7%	"	"	"	"	24/64"	24
c " F/180 BO	" 20%	"	"	"	"	24/64"	24

SIP# 1150 (a) FI TP # 240(b):150(c) FI CP# _____ SIBHP _____GOR. _____ GR. 40.3(b):38.6(c) BTBD 5889 TD 6009

SIZE	DEPTH	CASING - CEMENT RECORD	SIZE	DEPTH	W/SAX.
<u>7"</u>	<u>5989</u>	<u>455</u>			

OPERATOR Republic Natural WELL NO. 2 Wheatley "A" ELEV. 2752 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			Marmaton	5042	
			Cherokee	5192	
			Morrow	5519	
			Chester	5592	
			Ste Genevieve	5622	
			St Louis	5720	

Old Info: OTD 6009. 7" @ 5989 w/455 sx. Completed 5-5-61 from St Louis (5893-5908) IF F/78 BO + 6/10 BW/24 hrs.

New info: MICT. Re-entered 5-30-61.

P/10/5883-88, 20/5822-32. Set plug @ 5889. Ran tbq w/pkr @ 5777 Swb 55 BO + 4 BL/24 hrs from 5822-88. 2500 Ac. Swb & flod 157 BO/14 hrs. Flod 305 BO/24 hrs, 3/8" ck, FTP 150. Flod 171 BOPD, 18/64" ck, FTP 200. Calc flow 205 BO/24 hrs from 5822-88.

P/24/4890-96. Set BP @ 4950. Tbg & pkr @ 4854. Swb & flod 20 BO/6 hrs, gty 35°. 500 Ac. Swb & flod 34 BO/4 hrs, 28/64" ck, FTP 460, SIP 980/1 hr. Flod 118 BO + 10½ BW w/343 MCF/24 hrs, 3/8" ck, FTP 240. Flod 77 BO + 7.7 BW/24 hrs, 3/8" ck, FTP 130. Flod 75 BO + 8 BW/24 hrs, 3/8" ck, FTP 110.

A-8-167

SHEET NO. 2

MAP NO. _____

STATE Kansas COUNTY Seward SEC. 23 Twp 33 S Rge 31 W

OPERATOR Republic Natural LOC. NW SE

WELL NO. 2 FARM NAME Wheatley "A"

Set BP @ 4400.

P/20/4300-05. Tbg & pkr @ 4280. Ga 62 MCF. 1000 MA. Ga 3000 MCF (wet). 16 hr BD 900 MCF + 76 BFW, FTP 180, Sep pr 75. SQ 4300-05 w/DOC (50 sx). Swb 19 BSW/17 hrs. Re-SQ 4300-05 w/DOC (100 sx). Swb dry.

Re-P/20/4300-05. 500-15% Ac. Swb dry/NS. 1500 Ac. 8 hr BD 509 MCF + 11 BSW/8 hrs, FP 130, 3000 Ac. 10 hr BD 2299 MCF + 97 BSW & 1d, FTP 650.

Ran triple tubing - 2-3/8" tbg & pkr @ 5775. 2-1/16" tbg & pkr @ 4860. 1 1/2" tbg & pkr @ 4284.

From Toronto (4300-05). 10 min SIP1000, 15" BD 3837 MCF, 1/4" ck, FTP 200, 10 hr SIP 1150.

From Lansing (4890-96), SIP 290.

From St Louis (5822-88), SIP 0.

IP (75min BD) 2273 MCF, SIP 1150 from Toronto (4300-05)

OPERATOR Republic Natural

WELL NO. 2 Wheatley "A"

IP F/241 BO + 7% wtr/24 hrs, 24/64" ck, FTP 240, gty 40.3° from Lansing (4890-96).

IP F/180 BO + 20% wtr/24 hrs, 24/64" ck, gty 38.6°, FTP 150 from St Louis (5822-88).

Triple completion.

COMPLETE 8-14-61