

A-5-114

1879 DF ✓

MAP NO. _____

ELEV. 1869 GL

STATE Kansas COUNTY Clark SEC. 24 Twp 33 S Rge 22 W

OPERATOR John P. Booth - Tulsa, Okla. LOC. C SW/4


WELL NO. 1 FARM NAME Ella McMinimy FT. FROM _____ LINE

POOL Sitka (PD 5500) FT. FROM _____ LINE

FR. 3-15-61 SPUD 3-15-61 COMP. 5-10-61

CONT./GEOL. Patton Drilling Company

NAME PRODUCING INTERVAL		COMPLETION RECORD FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a	Morrow	5307-32	48	500 A-F/10X10
b				
c				
d				



I. P. OIL/DIST.	WTR.	COF	GAS	6300	M.C.F.P.D.	CHK.	HRS.
b	"	"	"	"	"	"	"
c	"	"	"	"	"	"	"
d							

D & A ()

SIP# 1300 FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBD TD 5440

SIZE	DEPTH	CASING - CEMENT W/SAX.	RECORD SIZE	DEPTH	W/SAX.
13-3/8"	38	4 yds	7"	2454	450
9-5/8"	460	150	4 1/2"	5440	300

OPERATOR John P. Booth WELL NO. 1 Ella McMinimy ELEV. 1879 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Morrow	5272		Elgin Sand	3995	
Morrow Sand Zone	5300		Elgin Sand	4116	
Morrow Sand	5315		Base Heebner	4225	
			Toronto	4244	
			Lansing	4414	
			Cherokee	5120	
			Morrow	5270	
			Morrow Sand Zone	5302	
			Morrow Sand	5322-33	
			Mississippian	5360	

Spud w/ratholer 3-15-61. 13-3/8" @ 38 w/4 yds. MIR. 9-5/8" @ 460 w/150 sx. 7"@ 2454 w/450 sx.

DST # 1 (Morr) 5288-5330, op 45 mins, GTS 2 mins, ga 4450 MCF/5 mins, ga 5594 MCF/15 mins (stabil), no fluid rec, ISIP 1940/15 mins, FP 695-665, FSIP 1915/30 mins.

RTD 5440, logs. 4 1/2" @ 5440 w/300 sx. MICT.

P/6/5307-09, 12/5314-18, 30/5322-32. 500 MA. Frac 10,000-3% Ac X 10,000 sd. Ga 4050 MCF, TP 200, CP 1000. Ga 5040 MCF, TP 225, CP 950.

IP COF 6300 MCF, SIP 300 from Morrow (5307-32) COMPLETE 5-10-61

5270
1879
3391
23