

5-418 + 84
MAP NO.

SEC. 24

TWP.

33S

RGE. 31W

STATE Kans. COUNTY Seward

LOC.

C SW SW

OPERATOR Panhandle Development Co.

FT. FROM

LINE

WELL NO. 1 FARM NAME Wheatley "B"

FT. FROM

LINE

WC-3 mi. NE Ang Pool (Miss & Cher Oil) ELEV. 2738 GR. 2745 DF. 2748 KBFR. 3/9/62 SPUD 3/26/62 COMP. 6/5/62CONT. McClellan Drlg. Tools /GEOL.

NAME PRODUCING INTERVAL

COMPLETION RECORD
FROM - TO

PERF. W/HOLES

TREATMENT RECORD

a. Morr 5653-3/4 4 Jet shot 500A & Frac

b. _____

c. _____

d. _____

St. Fl
d I. P. OIL/DIST. 241 BO WTR. NW GAS M.C.F.P.D. CHK. HRS. 24

b. " " " " "

c. " " " " "

d. _____

D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. 38.9° PBDT 5730 TD 5963

SIZE	DEPTH	CASING - CEMENT RECORD W/SAX.	SIZE	DEPTH	W/SAX.
<u>8-5/8"</u>	<u>1242</u>	<u>600</u>			
<u>4 1/2"</u>	<u>5777</u>	<u>150</u>			

OPERATOR Panhandle Dev. Co. WELL NO. 1 Wheatley "B" ELEV. 2748 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
KB Tops & Datums					
Hb	4301		CG	3078	- 330
Tor	4323		Hb	4295	-1547
Kc	4446		Tor	4334	-1586
RTD (St Gen)	5963	-3215	Lans	4450	-1702
			Marm	5094	-2346
DST #1 (Tor)	4334-48,		Chero	5267	-2519
Op 2 hrs, SB, R 90' MW +			Morr	5596	-2848
150' SW, IBHP 1250#/30",			Morr sd	5645	-2897
IFP 0#, FFP 0#,			St Gen	5882	-3134
FBHP 1040#/30"			LTD	5961	-3213
DST #2 (Morr)	5570-5690,				
Op 2 hrs, 900' GIP, R 210' GCM + 260' GOCM + 10' FO, no					
IBHP taken, IFP 140#, FFP 370#, FBHP 700#/30"					
RTD 5963, Log, LTD 5961					
1 shot WLT #1 5653 (Morr sd), Plugged,					
4 shot WLT #2 5652-54 1/2 (Morr sd) Op 61" (GOR less than					
(500-1) R 200 cc oil (Gr 35 deg) + 20,400 cc filt wtr,					
IBHP 2100#/10", IFP not avail, FBHP 2100#/10"					
4 1/2" @ 5777 w/150 sx, MICT & CO 5730 PBDT, Log, 4 Way Jet					

5654 3/4, tst show oil nat, A/500, \$ ld, swb 1 BFPH (70%
fresh wtr)/4 hrs, frac/5000 gal jell oil x sd/5000, swb
133 BL, flo 107 BL (Total), flo 12 BNOPH/NT/NW
State Pot: (5/28/62) flow 241 BOPD/NW, Morr Jet Shot
5653 3/4, G. 38.9°.

LIBERAL ELECTRIC LOG TOPS

2748 KB

Winfield 2732 (+16)

Heebner 4316 (-1568)

Toronto 4334 (-1586) tst XW

Lansing 4450 (-1702)

Marmaton 5102 (-2354)

Morrow 5596 (-2848)

"S-2" 5645 (-2897) 4/12, ϕ 241 BOPD

Chester 5752 (-3004)

Ste. Gen 5912 (-3164)

TD 5963