


11-153W
 MAP NO. OWWO SEC. 25 TWP. 33S RGE. 22W
 STATE Kans COUNTY Clark LOC. C SE/4
 OPERATOR Graham-Michaelis FT. FROM _____ LINE
 WELL NO. 1-25 FARM NAME Pfiefer(OWWO) (was Clark) FT. FROM _____ LINE
 POOL Stika ELEV. _____ GR 1870 0 PF 1872 0 KB
 FR. 10/16/62 SPUD _____ COMP. 11/13/62
 CONT. Co. tools _____ /GEOL. _____

NAME PRODUCING INTERVAL		COMPLETION RECORD		TREATMENT RECORD	
		FROM - TO	PERF. W/HOLES		
a.	<u>Morrow</u>	<u>5334-54</u>	<u>56</u>	<u>1000 A</u>	
b.	<u>Miss</u>	<u>5360-5406</u>	<u>56</u>	<u>500 A & Frac</u>	
c.					
d.	<u>Cal OF</u>				

d I. P. OIL/DIST. 0 WTR. 0 GAS 3800 M.C.F.P.D. _____ CHK. _____ HRS. 12
 b. " " " " " "
 c. " (COMINGLED GAS. - MORR & MISS) " "
 d. _____



D & A ()

SIPH 1650 FI TP # _____ FI CPH _____ SIBHP _____
 GOR. _____ GR. _____ PBTD _____ TD 5459
 Casing - Cement Record

SIZE	DEPTH	W/SAX.	SIZE	DEPTH	W/SAX.
<u>13-3/8" @</u>	<u>185</u>	<u>200</u>	<u>4 1/2"</u>	<u>5460</u>	<u>150</u>
<u>7" @</u>	<u>1993</u>	<u>560</u>			

OPERATOR Graham-Michaelis WELL NO. 1-25 Pfiefer(OWWO) ELEV. 1872 OKB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
OWWO			(Old KB Log Tops & Datums)		
OLD INFO			Chase Gr	2384	- 512
			Elgin sd	4040	-2168
OTD(St Gen)	5459	-3587	Hb	4212	-2340
			Tor	4236	-2364
New Info:			Lans	4428	-2553
RTD (St Gen)	5463	-3591	Marm	4984	-3112
Old Information: (Was Falcon-			Chero	5178	-3306
Seaboard) #1 Pfeifer			Morr	5290	-3418
WLT #1 4055(Elgin) Op 30", R			Chest	5356	-3484
10,000 cc filt wtr, ISIP			StGen	5366	-3494
1600#/5", IFP 0#, FFP 1600#,			Old LTD	N.A.	
FSIP 1600#/12".					

OTD 5459. no DST's, Comp. as D & A 12/21/60.

New Information: (10/16/62) MIRT. CO 5459 OTD & DD to RTD 5463,
 4 1/2" @ 5460 w/150 sx, Perf Miss 16/5402-06 & 24/5388-94, 500 A,
 Ga 108 MCFGPD. Frac (5000 gal acid x 3750# sd) Ga 1530 MCFGPD,
 Plg @ 5386, Perf Morr 16/5350-54 & 40/5334-44 & Perf Miss
 16/5360-72, 1000 A, CO 5410 PBTD, Frac (27000 gal acid x 17000#
 sd), Ga 3000 MCFGPD thru tbg, Cal OF 3800 MCFGPD/12 hours, SIP
 1650#. Comingled Morr & Miss 5334-5406. COMPLETED