

SIDE ONE

Ind 8/26/84
KCC

STATE CORPORATION COMMISSION OF KANSAS
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION OR RECOMPLETION FORM
ACO-1 WELL HISTORY

DESCRIPTION OF WELL AND LEASE

Operator: license # 8802
name COBRA OIL & GAS CORPORATION
address P.O. Box 1929
City/State/Zip Woodward, Oklahoma 73802

Operator Contact Person Glen A. Waugh
Phone 405-254-2027

Contractor: license # 5654
name Rine Drilling Company

Wellsite Geologist Bill Hillman
Phone 405-256-3877

Designate Type of Completion

☒ New Well ☐ Re-Entry ☐ Workover

☐ Oil ☐ SWD ☐ Temp Abd
☐ Gas ☐ Inj ☐ Delayed Comp.
☒ Dry ☐ Other (Core, Water Supply etc.)

If OWWO: old well info as follows:

Operator
Well Name
Comp. Date Old Total Depth

WELL HISTORY

Drilling Method: ☒ Mud Rotary ☐ Air Rotary ☐ Cable

8-12-84 8-24-84 8-26-84
Sp. Date Date Reached TD Completion Date

5925'
Total Depth PBDT

Amount of Surface Pipe Set and Cemented at 1215' feet

Multiple Stage Cementing Collar Used? ☐ Yes ☐ No

If Yes, Show Depth Set feet

If alternate 2 completion, cement circulated
from feet depth to w/ SX cmt

API NO. 15 - 119-20,674

County Meade

NW NE SE Sec 10 Twp 33S Rge 26 West
(location)

2140' Ft North from Southeast Corner of Section
980' Ft West from Southeast Corner of Section
(Note: locate well in section plat below)

Lease Name Goff "10" Well# 1

Field Name Wildcat

Producing Formation


Elevation: Ground 2264' KB 2276'

RELEASED

Date: SEP 1 1985

FROM CONFIDENTIAL

SEP 1 8 1985
State Geological Survey
WICHITA BRANCH



WATER SUPPLY INFORMATION

Source of Water:

Division of Water Resources Permit #

☐ Groundwater Ft North From Southeast Corner and
(Well) Ft West From Southeast Corner of
Sec Twp Rge ☐ East ☐ West

☐ Surface Water Ft North From Southeast Corner and
(Stream, Pond etc.) Ft West From Southeast Corner
Sec Twp Rge ☐ East ☐ West

☐ Other (explain)
(purchased from city, R.W.D.#)

Disposition of Produced Water: ☐ Disposal
☐ Repressuring

Docket #

INSTRUCTIONS: This form shall be completed in duplicate and filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Kansas 67202, within 90 days after completion or recompletion of any well. Rules 82-3-130 and 82-3-107 apply. Side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form. See rule 82-3-107 in excess of 12 months.

AUG 30 1984

SIDE TWO

Operator Name **Cobra Oil & Gas Corp.** ... Lease Name **Goff** 10 Well# **11** SEC. **10** TWP **33S** RGE. **26** ...

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken

Samples Sent to Geological Survey

Cores Taken

☒ Yes ☐ No
☒ Yes ☐ No
☐ Yes ☐ No

Formation Description

☒ Log ☐ Sample

DST #1 5530'-5630' 30-60-60-120 Mins. Rec 544'
 gas in pipe & 291' SGC salty mud. IHP 2709# IFP 140-
 156# ISIP 1551# FFP 202-234# FSIP 1612# FHP 2709#

DST #2 5667'-80' 30-60-60-120 Mins. Rec 5' drlg.
 mud. IHP 2724# IFP 31-16# ISIP 31# FFP 16-16#
 FSIP 31# FHP 2724#

DST #3 4812'-31' 30-60-60-120 Mins. Rec 2500'
 salt water. IHP 2330# IFP 59-408# ISIP 1631# FFP
 408-695# FSIP 1656# FHP 2305#

Name	Top	Bottom
Heebner	4352'	2076'
Toronto	4368'	2092'
Iatan	4430'	2154'
Lansing	4526'	2250'
KC	4622'	2346'
Swope LS	5026'	2748'
Hush Sh	5078'	2802'
Ft. Scott	5302'	3026'
Cherokee	5320'	3044'
Atoka	5482'	3206'
13 Finger	5520'	3244'
Chester	5582'	3306'
St. Gen.	5836'	3520'

CASING RECORD

☐ new ☐ used

Report all strings set - conductor, surface, intermediate, production, etc.

Purpose of string	size hole drilled	size casing set (in O.D.)	weight lbs/ft.	setting depth	type of cement	# sacks used	type and percent additives
Surface	12 1/4"	8 5/8"	24	1215'	Poz & reg.	750	

PERFORATION RECORD

shots per foot specify footage of each interval perforated

Acid, Fracture, Shot, Cement Squeeze Record

(amount and kind of material used)

Depth
