

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


19.33-26W

Company- MICHAELIS DRILLING CO.
Farm- Horner No. 1

SEC. 19 T. 33 R. 26W
C NE/4

Total Depth. 5720
Comm. 11-10-55 Comp. 12-10-55
Shot or Treated.
Contractor. Michaelis Drilling Co.
Issued. 1-21-56

County Meade
KANSAS



CASING:

13 3/8 @ 400' w/ 300 sx cmt.
5 1/2 @ 5717' w/ 200 sx cmt.

Elevation. 2280 KB

Production. 5,000,000 CFGPD

Figures indicate Bottom of Formations.

sand & gravel	25
red bed & sand	125
red bed	360
gyp & red bed	457
red bed & shale	800
red bed, sand, shale & anhydrite	1008
red bed & shale	1340
red bed & shale w/ anhydrite streaks	1815
red bed & shale	2075
shale & anhydrite streaks	2235
shale & lime	2405
lime w/ shale streaks	2495
lime & shale	3130
lime & shale w/ bentonite	3275
lime & shale	4542
Lansing lime	4575
lime	5656
lime, sand & shale	5696
lime	5720
Total Depth	

SCOUT TOPS:

Herington	2460
Winfield	2590
Lansing	4541
Morrow shale	5615
Chester	5669