

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company- GULF COAST RICE FARMS, INC.  
Farm- M.A. Horner No. 1

SEC. 30 T. 33 R.26W  
C NW 1/4 C NE

Total Depth. 6096' Schl. 6113' Driller,  
Comm. 4-20-53 Comp. 7-20-53  
Shot or Treated.  
Contractor.  
Issued. 6-8-57

County Meade

KANSAS



Elevation. 2311' KB

Production. 4,630,000 CFG.

CASING:

9 5/8" 627'  
5 1/2" 5897'

Figures indicate Bottom of Formations

NO DRILLERS LOG AVAILABLE.

SAMPLE LOG 2000' to T.D.

red & gry, anhydritic shale	2000	TOPS:		
Buff-tan dolomite	2540	Hollanberg	SAMPLE	SCHL.
Buff, coarse Wln, fossiliferous,		Herrington	2540	2545
porous limestone	2800	Ft. Riley		2588
Gry-tan, cherty, limestone	2880	Florence	2800	2810
gry-white, dense, fossili-		Topeka	2880	2880
ferous limestone	3060	Heebner	3640	3640
gry, fine grained, calcareous		Lansing	4420	4410
sand	3150	Morrow shale	4640	4610
gry, dense, fxln; fossili-		Chester	5695	5692
ferous limestone, pinpoint		St. Genevieve	5720	5720
porosity	3300		6067	6065
gry to tan, dense, fossili-				
ferous, cherty limestone	3640			
gry to tan, dense, fossili-				
ferous, cherty limestone				
w/tr gry shale	3690			
dk-gry, shaly, limestone				
& gry shale	3740			
lght-gry, medium grained,				
calcareous sandstone	3900			
Varicolored shales w/light				
gry calcareous sandstone	3960			
dk-gry, shaly limestone	4150			
gry, slity, limy, fine				
grained sandstone	4270			
dk-gry, shaly limestone	4300			
gry, silty, limy sandstone				
& gry micaceous shale	4350			
Blk, brittle, carbonaceous,				
shale	4420			
lght-gry, creamy, dense lime-				
stone	4460			
Brwn, dense, cherty, fossiliferous				
limestone	4640			
Gry to gry-buff, fossili-				
ferous, Mxln limestone	4990			
Tr. sandstone(quartz grains)	5200			
dk.-gry., sdy shale	5530			
Splintery blk. shales; dk-				
brwn, dense, cherty lime-				
stone	5590			
gry-grn, micaceous, flaky				
shale	5660			
dk-gry, dense, Fxln, shaly				
limestone	5680			
Hrd, Fxln, crinoidal, gry				
to buff-brwn limestone	5720			
gry to brwn, fossiliferous,				
shaly limestone	5770			
blk shale	5850			
gry, Fzln, fossiliferous,				
tght limestone w/blk shale	5900			
Total Depth	5930			
SCHLUMBERGER T.D.	6096			
Driller T.D.	6613			