

KANSAS

IMPORTANT
Kans. Geo. Survey request samples on this well.

WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 15 — 119 — 20,400
County Number

Operator
Hawkins Oil & Gas, Inc.

Address Box 1578 Liberal, Kansas 67901
1869

Well No. #1-36 Lease Name Thisis

Footage Location
660 feet from (N) (S) line 660 feet from (E) (W) line

Principal Contractor DaMac Drilling, Inc. Geologist Don L. Huber

Spud Date 6-6-80 Date Completed 6-18-80 Total Depth 6023 P.B.T.D. 5975


Directional Deviation No Oil and/or Gas Purchaser

S. 36 T. 33 R. 26 ^W

Loc. C SE SE

County Meade

640 Acres



Locate well correctly

Elev.: Gr. 2269'

DF 2278' KB 2280'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8	24#	1472'	35/65 poz Class H	700 6% 250	gel, 2% cc, 1/4# cel 2% cc flal
Production	7 7/8	4 1/2	10.5#	6015'	1st stage & 2nd stage Class H	50	8% gel, 12 1/2# Gilsco ite, 10% salt
					50/50 poz	150	18% salt, 12 1/2# Gilsco sonite, .75% TIC
					DV tool @ 3194' KB		

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1	.38 DP	5743-51; 5717-20

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8"	5696	5696

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1500 gal. 15% Spearhead acid 6000 gal West Pad A + 6000 gal 15% Series 70 acid w/1200 scf/bbl CO ₂	5717-20; 5743-51

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
Shut in - waiting on gas sales contract	flowing
RATE OF PRODUCTION PER 24 HOURS	Gas-oil ratio
Oil Trace bbls. Gas 300 MCF Water 2 bbls.	CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval(s)
To be sold	5717-5751 Chester

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Hawkins Oil & Gas, Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Gas

Well No.

1-36

Lease Name

Theis

S 36 T 33S R 26 E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

Surface Sand
Shale
Shale, Lime
Lime

0
1480
2370
5678

1480
2370
5678
6023 RTD

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Ned E Lowry
Signature

Agent/Hawkins Oil & Gas, Inc.

Title

August 15, 1980

Date

36-33-26W

PLAT AND CERTIFICATION OF ACREAGE ATTRIBUTABLE TO A GAS WELL

State Corporation Commission, Conservation Division
245 North Water Wichita, Kansas 67202

OPERATOR Hawkins Oil & Gas, Inc.

LOCATION OF WELL

LEASE This

660 feet from the South line

WELL NUMBER 1-36

660 feet from the East line

Of the SE/4 of Sec. 36 T. 33S R. 26W

FIELD _____

COUNTY Meade

ORDER GRANTING ALLOWABLE ENTERED IN DOCKET NO. _____

NUMBER OF ACRES
ATTRIBUTABLE TO WELL 320

DESCRIPTION OF ACREAGE:

PLAT

(Show location of Well and outline attributable acreage)

