


11-258W Map No. 85OPER M M & B, INC.
ENGLEWOOD, COLORADOWELL #1 SHEETZR GARVEY TOOLSFIELD EXT - MC KINNEY FIELD (MRW, MISS)I.P. CAL OF GA 5,200,000 CFGPDCHEST 5725-77S-T-R 27-33S-26WSPOT C SW SWCO MEADE, KS.ELEV 2280 KB

KB LOG:

C.G. 2852 - 572

B/HB 4395 -2115

LAN 4560 -2280

MAR 5209 -2929

13 FING

LM 5614 -3334

B/ " 5651 -3371

MRW LM 5657 -3377

CHEST 5696 -3416

B/U. CHEST

5789 -3509

LTD 5853 -3573

RTD 5850 -3570

SPUD 9-23-66, 8" 1289 W/750 SX

GEOL - W. E. LITTLE

DST #1 (LAN) 5066-5108, OP 10, SI 45, OP 30, SI 45, R 2' MUD

ISIP 82#/45", FP'S 35-35#, FSIP 35#/45"

DST #2 (MRW) 5649-5705, OP 15, SI 45, OP 30, SI 45, R 10'

MUD, ISIP 110#/45", FP'S 73-73#, FSIP 73#/45"

DST #3 (CHES) 5700-5750, OP 15, SI 30, OP 30, SI 45, GTS 17"

GA 121,000 CFGPD/10", GA 213,000 CFGPD/90" (NOT STAB)

R 120' GCM, ISIP 1229#/45", FP'S 73-73#, FSIP 1220#/90"

RTD 5850, SCHLUMBERGER LOG, 5½" 5840/CEM

PF 36/5768-77, (CHEST) 1000A, GA 255,000 CFGPD, 3/4" CK,

TREAT W/10,000A, GA 1,630,000 CFGPD, 18/64" CK, FTP 460#,

SET PKR 5749, PF 40/5725-35 (CHEST) TREAT W/7000A, FLO

1,250,000 CFGPD, 20/64" CK, FTP 420#, FCP 600#, CO 5800 PBDT

CAL OF GA 5,200,000 CFGPDCHEST 5725-77COMPLETED 11-15-66Data Inc

MISCEL DATA

GEOL W. E. LITTLE

FTG

SUPPT

CSG 8" 1289/750 SX 5½" 5840/CEMELEV 2272 GR2278 DF252382 DFSPUD DATE 9-23-66

DRLG COMP

FR by DATA 8-31-66COMP by " 12-1-66