


1-183W  
 MAP NO. \_\_\_\_\_ 1844 GR ELEV. 1852DF 1854KB  
 STATE Kans COUNTY Clark SEC. 26 TWP. 33S RGE. 21W  
 OPERATOR Graham-Michaelis Drlg Co. loc. App C NW SE  
 WELL NO. 1-26 FARM NAME Carthrae 1985 FT. FROM S LINE  
 POOL Harper Ranch 1975 FT. FROM E LINE  
 FR. 10/23/61 SPUD 10/21/61 COMP. 1/16/62

CONT./GEOL. Co Tools.

COMPLETION RECORD  
 NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD  
 a Morr sd 5378-85 28 500 A & Frac



b \_\_\_\_\_  
 c \_\_\_\_\_  
 d WH OF  
 I. P. OIL/DIST. 0 WTR. 0 GAS 7766 M.C.F.P.D. \_\_\_\_\_ CHK. \_\_\_\_\_ HRS. 24  
 b " " " " " "  
 c " " " " " "  
 d \_\_\_\_\_

SIP# 1750#/72 hrs FI TP # \_\_\_\_\_ FI CP# \_\_\_\_\_ SIBHP \_\_\_\_\_

GOR. \_\_\_\_\_ GR. \_\_\_\_\_ PBTD 5390 TD 5440  
 CASING - CEMENT RECORD  
 SIZE DEPTH W/SAX. SIZE DEPTH W/SAX.  
13 3/8" 362 300  
4 1/2" 5439 135

OPERATOR Graham-Michaelis WELL NO. 1-26 Carthrae ELEV. 1854 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Sinclair & Hugoton Prod - FO					
KB Tops & Datums					
Hb	4283	-2429	Lans	4467	-2613
Tor	4308	-2454	Mam	5027	-3173
Lans	4469		Morr Sh	5292	-3438
TD (Miss)	5440	-3586	Morr sd	5328	-3474
			Morr sd	5376-88	-3522
			Miss	5403	-3549
			LTD (Miss)	Not avail.	
DST #1 (Morr sd) 5378-90, (Str Pkr) Op 1 hr, GTS/3" Ga 442 Mcfgpd/5", Ga 110 Mcfgpd/45" & Stab, R 30' GCM + 80' GCMW, IBHP 1928#/30", IFP 134#, FFP 242# FBHP 1928#/30".					
DST #2 (Morr sd) 5330-54 (Str Pkr) Op 1 hr, R 50'M, IBHP 80#/20", IFP 26#, FFP 26#, FBHP 53#/20". RTD: 5440 (Miss) Log. 4 1/2" @ 5439 w/135 sx. CO 5390 PBTD, 28/5378-85 (Morr) 500 A, Ga 6270 Mcfgpd Frac (10,000# sd x 10,000 A), Ga 8000 Mcfgpd, no flu WH OF Ga 7766 Mcfgpd, SICP 1750#/72 hrs. Morr sd 5378- 85. COMPLETED					