


FR & COMP

10-290W MAP NO. K-84 OWWO SEC. 26-33S-31W
 STATE Kansas COUNTY Seward LOC. SE SE NW
 OPER. Panhandle Dev. Inc. - Liberal, Kansas FT/FR _____ LINE _____
 WELL #1 FARM Jury FT/FR _____ LINE _____
 COL Kismet ELEV. _____ GR. 2735 DF 2738 KB _____
 CONT. _____ GEOL. _____
 CO. _____
 INT. _____
 F.R. 10-16-64 SPUD Aug-1952 COMP. 10-27-64
 TD. 5910 FM. Ste Gen P.B.T.D. 4330
 Tor 4308-13 20 500A
 State Pot: P 149 BOPD - NW Gr 43.1 deg
 8" NA 5" @5856'



Data Inc.

OLD INFO: Was Flynn Oil Co. #1 Jury

(KB Log Tops:)

Tor 4303-1565

Lans 4430-1692

Mrw sh 5530-2792

Miss 5581-2843

Ste Gen 5682-2944

OTD 5860-3122

DD TD 5910-3172

OTD 5860' 5" @5856' Completed as
oil well from Ste Gen pfs 5856-60
on 10-3-52

Re-work: Purchased by Russell J.
Cobb, Jr. MICT, DD 5910 TD, tbg w/
pkr @5860, \$ 10 BOPH / 2 BWP/NT, \$
10 BFP/ (95% W)/8 hrs, abdn zone
5860-5910 Comp as oil well from

original pfs 5856-60 (Ste-Gen)

NEW INFO: MICT 9-3-64 PB 4435, 4-way jet @4360 (Lans) &
sqz w/150 Sx. CO 4435, 4-way 4320 (Lans) sqz w/75 sx., CO
4416, 20/4308-13 (Tor) \$ 7 BWP/ w/tr gas, sqz 4308-13, w/100
sx., CO 4330 P.B.T.D., 20/4308-13 (Tor), tbg w pkr @4300 \$ dry
w/sho gas, 500A, \$ 1d, flo 14 BOP/NT, (Gr 37.8 deg) 1500A,
\$ 1d & flo 22 BOP/ - NW / little gas/3 hrs, pull tbg & pkr
POP, State Pot 9-22-64, P 149 BO - NW/24 hrs, Gr 43.1 deg
Tor 4308-13 FIRST REPORTED & COMPLETED 10-16-64